

3081 McNab Warehouse

3081 MCNAB ROAD
POMPANO BEACH, FLORIDA 33069

ARCHITECTURAL:

- A-0.0 COVER SHEET
- A-0.1 SITE PLAN
- A-0.2 DEMO PLAN
- A-0.3 CPTED PLAN
- A-1.0 FLOORPLAN
- A-1.1 LIFE SAFETY
- A-3.0 ROOF PLAN
- A-4.0 EXISTING & PROPOSED SOUTH ELEVATION
- A-4.1 EXISTING & PROPOSED NORTH ELEVATION
- A-4.2 EXISTING & PROPOSED EAST ELEVATION
- A-4.3 EXISTING & PROPOSED WEST ELEVATION

CIVIL:

- COVER SHEET
- PD1 PAVING, GRADING AND DRAINAGE PLANS
 - PD2 PAVING, GRADING AND DRAINAGE DETAILS
 - WS1 WATER AND SEWER PLANS
 - WS2 WATER AND SEWER DETAILS
 - SPP1 STORMWATER POLLUTION PREVENTION PLAN

LANDSCAPE:

- LP1 LANDSCAPE PLAN
- LP2 SPECIFICATIONS AND DETAILS
- IR1 IRRIGATION PLAN
- TR1 TREE DISPOSITION PLAN

ZONING CLASSIFICATION: I-1 General Industrial
OCCUPANCY CLASSIFICATION: S-1 per FBC 306.2
General Industrial per NFPA 101-40.1.2.1.1

WAREHOUSE USE:

EXIST'. CONSTRUCTION TYPE: TYPE V - (NON- SPRINKLERED)
NEW CONSTRUCTION TYPE: III-B (FULLY SPRINKLERED)

MAX. LOT COVERAGE: 65%
PROPOSED LOT COVERAGE: 36.26 %
MAX. ALLOWABLE BLDG. HT: 45'-0"
PROPOSED MAX BLDG HT: 23'-10"

Note: As defined in Section 155.9401.G: *General Height Measurement: "The height of a structure shall be determined by measuring the vertical distance from the average elevation of the existing finished grade at the front of the structure to the top of the roof for a flat roof....."*

SETBACK DATA PER ZONING REGULATIONS

REQUIRED	PROPOSED
Front : 25 ft Street Side: 10 ft Waterway or Canal: 15 ft Interior Side: 10 ft Rear : 30 ft	Front (W McNab Rd) : 61'-6" Street Side (SW 31st Ave) : 80'-10" Canal: 15'-0" Interior Side: N/A Rear (North) : 34'-9"

TOTAL SITE AREA: 90,827 sf /2.0851 AC.

GROSS BUILDING AREA : 39,376 sf
Existing Ground Floor Whse 13,296 sf (9,553 sf - 21ft clear Rack Storage)
Existing Ground Floor Whse 2,704 sf (Office)
Existing Second Floor Whse 6,447 sf (9ft clear Shelving Light Storage)
New Ground Floor Whse 16,929 sf (21ft clear Rack Storage)

PERVIOUS AREA

MIN. PERVIOUS AREA REQUIRED: 18,165 SF (20.00%)
TOTAL PERVIOUS AREA PROVIDED: 22,433 SF (23.15%)

INTERIOR GREEN AREA REQUIRED: (15.00% of VUA): 4,916 SF
INTERIOR GREEN AREA PROVIDED: (15.65% of VUA): 5,457 SF

IMPERVIOUS AREA

- Building area (Lot Coverage): 32,929 SF (36.26%)
- Miscellaneous Concrete: 2,671 SF (4.68%)
(Conc Walk & Ramps/Dumpster/Aprons)
- Vehicular Use Area (VUA): 32,794 SF (35.91%)

TOTAL IMPERVIOUS AREA: 68,394 SF
(Including Building Footprint)

PARKING STATS


TOTAL PARKING REQUIRED : 25 Stalls (Incl 1 HC)
TOTAL PARKING PROVIDED: 38 Stalls (Incl 2 HC)

Office Area: (Typical Business Office Uses)
2,704 sf @ 1 per 400 sf = 7 Stalls
Whse Area: (Warehousing/Distribution/Storage)
36,672 sf @ 1/750 sf for 1st 3k sf = 4 Stalls
Remaining 33,672 sf @1/2,500 sf = 14 Stalls

LOADING BERTHS REQUIRED: 2
LOADING BERTHS PROVIDED: 3

4 BICYCLE SPACES FOR EVERY 10 VEHICLE
PARKING SPACES PROVIDED (NOT TO EXCEED 20 SPACES)

TOTAL BIKE SPACES REQUIRED: 16
TOTAL BIKE SPACES PROVIDED: 16



PROJECT LOCATION



VICINITY MAP

ALL WORK TO COMPLY WITH THE FOLLOWING CODES:

THIS PROJECT IS TO BE BUILT IN ACCORDANCE WITH ALL CITY OF POMPANO BEACH BUILDING DEPARTMENT REQUIREMENTS AND AMENDMENTS, BROWARD COUNTY REQUIREMENTS AND FOLLOWING CODES:

- 2023 FLORIDA BUILDING CODE
- 2023 FLORIDA BUILDING CODE - ACCESSIBILITY
- NATIONAL ELECTRICAL CODE 2023
- 2023 THE FLORIDA FIRE PREVENTION CODE
- NFPA-101, 2018 EDITION W/ FLORIDA AMENDMENTS
- NFPA 1 UNIFORM FIRE CODE 2018 W/ FLORIDA AMENDMENTS
- FLORIDA STATUTES
- FLORIDA ADMINISTRATIVE CODE

NOTE: TO THE BEST OF THE ARCHITECT'S KNOWLEDGE, THE PLANS AND SPECIFICATIONS COMPLY WITH THE APPLICABLE MINIMUM BUILDING CODES AND APPLICABLE FIRE-SAFETY STANDARDS AS DETERMINED BY THE LOCAL AUTHORITY IN ACCORDANCE WITH SECTION 110 OF THE PBC ADMINISTRATIVE CODE AND CHAPTER 633 OF THE FLORIDA STATUTES

NOTE: THE PROJECT IS PURSUING LEED CERTIFICATION. THE OWNER HAS ENGAGED COMMISSIONING AUTHORITY FOR FUNDAMENTAL AND ENHANCED COMMISSIONING SERVICES. PLEASE REFER TO LEED PROJECT MANUAL FOR MORE INFORMATION.

DRAWING INDEX

APPLICANT:
BLUEWATER BUILDERS, INC.
2921 North Australian Avenue
West Palm Beach FL 33407
Contact: Todd Nezwek
T 954-868-5698
E tnezwek@bluewaterbuilders.cc

LANDSCAPE:
AGT LAND
132 North Swinton Avenue
Delray Beach, FL 33444
T 561-276-5050
E carol@agtland.com

OWNER:
PERLA RUBBIN & SONS USA, INC.
3908 NW 126th/ Avenue
Coral Springs, FL 33065
T 786-449-4005
E Sales@oceansouth.us

ARCHITECT:
HNM ARCHITECTURE, LLC
143 South Swinton
Delray Beach, FL 33444
Contact: Jaime O. Mayo
T 561-733-2225
E jmayo@hnm-architecture.com

CIVIL:
SUN-TECH ENGINEERING, INC
4577 Nob Hill Road, Suite#102
Sunrise, FL 33351
T 954-777-3123
E cloutan@suntecheng.com

PROJECT TEAM

PROJECT STATS

NOTES

3081 McNab Road

Project at
3081 McNab Rd, Pompano Beach, Florida 33069

NO. DATE
REVISION

ALL DRAWINGS, SPECIFICATIONS AND RELATED DOCUMENTS ARE THE COPYRIGHT PROPERTY OF THE ARCHITECT AND MUST BE RETURNED UPON REQUEST. REPRODUCTION OF DRAWINGS, SPECIFICATIONS AND RELATED DOCUMENTS IN PART OR WHOLE IS FORBIDDEN WITHOUT THE ARCHITECT'S WRITTEN PERMISSION.

CONTRACTOR MUST CHECK AND VERIFY ALL DIMENSIONS AND FIELD CONDITIONS AND NOTIFY ARCHITECT/ENGINEER IMMEDIATELY OF ANY DISCREPANCIES.

HNM
HNM ARCHITECTURE
3705 North Federal Highway • Delray Beach, Florida 33483 • T 561-733-2225
info@hnm-architecture.com • AIA20000708 • www.hnm-architecture.com

Digitally signed
by Michael
Hanlon
Date:
2024.09.17
13:51:24-04'00'

MICHAEL W. HANLON
FLORIDA REGISTERED ARCHITECT - REG. NUMBER: AR0017270

ELECTRONIC SIGNATURE SERIAL NUMBER:

HNM PROJECT NUMBER:
23-055

ISSUED DATE:
2020-09-17

SCALE:
AS NOTED

TITLE:
COVER SHEET

NUMBER

AR-0.0

PZ24-12000016
10/16/2024