



8	AT BUILDING / CURB	
	PLAN	NOT TO SCALE



7 GROUNDCOVER PLANTING



9 BUTTER SECTION SECTION NOT TO SCALE



6 GROUND COVER PLANTING



5 PLANTING DETAIL



4 SECTION NOT TO SCALE



3 PALM PLANTING DETAIL



2	TREE PLANTING DETAIL	
	SECTION	NOT TO SCALE



1	TREE PLANTING DETAIL	
	SECTION	NOT TO SCALE

120°

120°

PRUNE AND TIE FRONDS TOGETHER WITH BIO-DEGRADABLE TWINE (MIN. 6-8 FRONDS); HURRICANE CUT MAY BE ACCEPTABLE

SABAL PALMS TO BE "SLICK" UNLESS OTHERWISE NOTED ON PLANT LIST

(5) - 2"x4"x18" WOOD BATTENS. ATTACH WITH 2 STEEL BANDS; DO NOT NAIL BATTENS TO PALM. HEIGHT OF BATTENS SHALL BE LOCATED IN RELATION TO THE HEIGHT OF THE PALM FOR ADEQUATE BRACING.

MINIMUM (3) - 2x4 WOOD BRACES. NAIL TO BATTENS AND TO 2x4 STAKES (DO NOT PIERCE TRUNK).

TOP OF ROOTBALL TO BE EVEN OR 1" ABOVE FINISH GRADE; BACK FILL WITH CLEAN SAND OR SPECIFIED PLANTING SOIL; REF. LP-001, SECTION M

NOTES:

- FINAL TREE STAKING DETAILS AND PLACEMENT TO BE APPROVED BY LANDSCAPE ARCHITECT
- ASSURE PERCOLATION OF ALL PLANTING PITS PRIOR TO INSTALLATION

— SINGLE LEADER (NO
CO-DOMINANT LEADERS, NO
INCLUDED BARK)
NOTE: TREES TO BE B&B
UNLESS SPECIFIED OTHERWISE

— "WELLINGTON" TAPE OR APPROVED EQUAL. 3 GUYS PER TREE, SPACED EQUALLY AND LOCATED ABOVE THE FIRST LATERAL BRANCHES; SECURE TO SISAL ROPE WRAPPED AROUND TRUNK

- TOP OF ROOTBALL TO BE EVEN OR 1" ABOVE FINISH GRADE
- 3" SPECIFIED MULCH; MIN. 18" RADIUS FROM TRUNK, PULL BACK 6" FROM TRUNK
- ORANGE WARNING TAPE 12" ABOVE GRADE

- 4" HEIGHT CONTINUOUS SOIL BERM / RETENTION BASIN
- REBAR (#3) OR WOODEN STAKES (TYP) BURIED BELOW GRADE
- BACKFILL WITH SPECIFIED PLANTING MIX; REF. LP-001, SECTION M.

— ONCE INSTALLED, REMOVE 1/3 BURLAP AND ALL WIRE AND NON-BIODEGRADABLE MATERIAL FROM THE ROOTBALL

STATISTICS: DPEI IMINABV