

GENERAL NOTES:


- 1.) CONTRACTOR TO VERIFY DEPTH AND LOCATION OF EXISTING UTILITIES PRIOR TO ANY CONSTRUCTION.
- 2.) ANY CITY OWNED SEWER MANHOLE WILL HAVE THE INTERIOR OF THE MANHOLE SEWPER COATED PER CITY ENGINEERING MANHOLE DETAILS 213-1, 214-1, 215-1 AND 216-1.
- 3.) ANY EXISTING WATER AND/OR SEWER CONNECTION TO THE SUBJECT LOTS NOT ELIMINATED MUST BE CUT AND CAPPED AT THE WATER MAIN IF A WATER SERVICE AND CUT OUT AND SLEEVED IF A SEWER LATERAL. SEWER LATERALS THAT ARE CUT AND CAPPED WILL NEED TO BE AS-BUILT PER OUR ENGINEERING AS-BUILT STANDARDS. IF THE EXISTING MAIN IS CLAY PIPE AND HAS A CIPP LINER CURRENTLY INSTALLED, (INSTALL A SECTIONAL LINER IN THE MAIN OVER THE OLD LATERAL THUS ELIMINATING THE LATERAL). IF THE EXISTING MAIN IS CLAY PIPE, (DIG DOWN CUT OLD CLAY PIPE, SLEEVE BACK IN WITH PVC AND CITY APPROVED COUPLINGS). IF THE EXISTING MAIN IS CLAY PIPE AND YOU ARE REQUIRED TO RETIRE MULTIPLE LATERALS FOR A PROJECT, (IT MAY BE CHEAPER FOR THE CONTRACTOR TO INSTALL A CITY APPROVED CIPP LINER FROM MANHOLE TO MANHOLE AND REMOVE THE LATERALS THAT THEY ARE RETIRING). IF THE EXISTING MAIN IS PVC PIPE, (REMOVE THE LATERAL PIPE FROM THE PVC WYE FITTING AND INSTALL A PLUG INTO THE WYE, INSTALL A GREEN LOCATION MARKING BALL AT THE LATERAL LOCATION, NO DEEPER THAN 4 FT. BELOW GRADE)

ESTIMATED WATER DEMANDS:
38.96 GPM (AVG.), 155.86 GPM [224,434 GPD] (PEAK)
ESTIMATED REQUIRED FIRE FLOW = 1,500 GPM

ESTIMATED SEWER DEMANDS:
38.96 GPM (AVG.), 155.86 GPD [224,434 GPD] (PEAK)

[illegible]

CAULFIELD & WHEELER, INC.
CIVIL ENGINEERING - LAND PLANNING
LANDSCAPE ARCHITECTURE - SURVEYING
7900 GLADES ROAD - SUITE 100
BOCA RATON, FLORIDA 33434
PHONE (561)-392-1991 / FAX (561)-750-1452



OAKS @ PALM AIRE
CONCEPTUAL WATER DISTRIBUTION &
SANITARY SEWER PLAN
POMPANNO BEACH, FLORIDA

DATE 04/03/2023
DRAWN BY RHT
F.B./ PG. N/A
SCALE 1"=50'

RYAN D. WHEELER
PROFESSIONAL ENGINEER
LICENSE NO. 71477
STATE OF FLORIDA
- FOR THE FIRM -
DATE Jan 29, 2025

JOB #10326
SHT.NO.
WS.01
OF 8 SHEETS