



NOTES:

- UNDERGROUND UTILITY LINES SHALL BE MAINTAINED AROUND THE TREE PROTECTION AREA WHERE POSSIBLE. IF NOT POSSIBLE, A TUNNEL MADE BY A POWER-SHOWN GOLF SMOKE MAY BE USED UNDER THE TREE.
- INSTALLATION OF FENCES AND WALLS SHALL BE DONE IN CONFORMANCE WITH THE ROOT SYSTEMS OF EXISTING TREES. ROOTS SHALL BE CUT BY HAND AND REPAIRED TO MAINTAIN 30° VNE SHAPES TO MAINTAIN ROOTS.
- NO DEVELOPMENT OR DEMOLITION ACTIVITY—including GRADING, THE OPERATION OR PARKING OF HEAVY EQUIPMENT OR THE REMOVAL OF ANY MATERIAL—SHALL BE ALLOWED WITHIN THE TREE PROTECTION AREA.
- CONTRACTOR TO INSTALL PROTECTIVE FENCE BARRIER AROUND EXISTING TREES TO REMAIN—AT THE START OF THE PROJECT—FENCE TO REMAIN IN PLACE THROUGHOUT THE DURATION OF THE PROJECT.

Diagram labels:

- OVERALL DIMENSION TO BE LOCATED AT DRIPLINE
- DRIPLINE
- FENCE TO EXTEND TO THE EDGE OF THE DRIPLINE OR MORE WIDE POSSIBLE
- THREE ROWS OF SPLIT RAIL FENCING (2x4) TO BE PLACED AROUND EXISTING TREES TO REMAIN
- WOODEN STAKES (2x4) 4" x 4" WITH 6" SPACINGS—TO SUPPORT SPLIT RAIL FENCING

REVISEMENTS		URBAN FORESTRY CITY OF POMPANO BEACH	LANDSCAPE STANDARDS	
BY:	DATE:		TREE PROTECTION DETAIL	
TCW	04/2019			
AS	09/2021		APPROVED BY: _____  URBAN FORESTER	DATE: SEP 2021 DWG. NO. <b>104-1</b>
		SCALE: N.T.S.		

Drawn <b>GSLA</b>	Field <b>LANDSCAPE ARCH</b>
Verified <b>KG</b>	Scale <b>as shown</b>
Approved <b>KG</b>	Date <b>10-09-2024</b>
Project Manager <b>KG</b>	Dwg. no. <b>L-000</b>
Project <b>24-838</b>	