




Hydraulic Analysis by HydraCALC

**Received after DRC Meeting  
to address DRC comments  
prior to the submission of a  
Building Permit Application.**

**1/27/2022**

SUMMERS FIRE SPRINKLERS, INC  
751 PARK OF COMMERCE DR, #100  
BOCA RATON, FL 33487  
MICHELLE MEISEL, P.E. #45316  
561-393-6718



Digitally  
signed by  
Michelle L.  
Franklin  
Date:  
2022.01.26  
19:39:07<sup>®</sup>  
-05'00'

Job Name : Bldg#1 UNIT B  
Drawing : 1  
Location : 117 S RIVERSIDE DRIVR, POMPAN0 BEACH FL  
Remote Area : B  
Contract : B922  
Data File : Bldg#2 UNIT E Fire Plans-rev-calc Area 2.WXF

HYDRAULIC DESIGN INFORMATION SHEET

Name - RIVERSIDE TOWNHOMES Date - 1/2022  
Location - 117 S RIVERSIDE DRIVR, POMPANO BEACH FL  
Building - 1 System No. - B  
Contractor - SUMMERS FIRE SPRINKLERS, INC Contract No. - B922  
Calculated By - CD Drawing No. - FP-2  
Construction: ( ) Combustible ( ) Non-Combustible Ceiling Height  
OCCUPANCY -

S Type of Calculation: ( ) NFPA 13 Residential (X) NFPA 13R ( ) NFPA 13D  
Y Number of Sprinklers Flowing: ( ) 1 ( ) 2 (X) 4 ( )  
S ( ) Other  
T ( ) Specific Ruling Made by Date  
E  
M Listed Flow at Start Point - Gpm System Type  
Listed Pres. at Start Point - Psi (X) Wet ( ) Dry  
D MAXIMUM LISTED SPACING 16 x 16 ( ) Deluge ( ) PreAction  
E Domestic Flow Added - Gpm Sprinkler or Nozzle  
S Additional Flow Added - Gpm Make TYCO Model LFII  
I Elevation at Highest Outlet - Feet Size 1/2 K-Factor 4.9  
G Note: Temperature Rating 175  
N

Calculation Gpm Required 59.26 At Test  
Summary C-Factor Used: Underground 140

W Water Flow Test:  
A Date of Test -  
T Time of Test -  
E Static (Psi) - 80  
R Residual (Psi) - 77  
Flow (Gpm) - 1306  
S Elevation - 2.6  
P Location:  
P  
L Source of Information:  
Y

Received after DRC Meeting  
to address DRC comments  
prior to the submission of a  
Building Permit Application.

1/27/2022

Tank or Reservoir:  
ap.  
lev.  
Well  
Proof Flow Gpm


# Water Supply Curve

SUMMERS FIRE SPRINKLERS, INC  
Bldg#1 UNIT B

Page 2  
Date

City Water Supply:  
C1 - Static Pressure : 80  
C2 - Residual Pressure: 77  
C2 - Residual Flow : 1306

Demand:  
D1 - Elevation : 2.196  
D2 - System Flow : 54.26  
D2 - System Pressure : 25.130  
Hose ( Demand ) : 5  
D3 - System Demand : 59.26  
Safety Margin : 54.860



# Fittings Used Summary

SUMMERS FIRE SPRINKLERS, INC  
Bldg#1 UNIT B

Page 3  
Date

## Fitting Legend

Abbrev.	Name	1/2	3/4	1	1 1/4	1 1/2	2	2 1/2	3	3 1/2	4	5	6	8	10	12	14	16	18	20	24
E	NFPA 13 90' Standard Elbow	1	2	2	3	4	5	6	7	8	10	12	14	18	22	27	35	40	45	50	61
Fsp	Flow Switch Potter VSR	Fitting generates a Fixed Loss Based on Flow																			
T	NFPA 13 90' Flow thru Tee	3	4	5	6	8	10	12	15	17	20	25	30	35	50	60	71	81	91	101	121
Zaf	Ames 3000SS	Fitting generates a Fixed Loss Based on Flow																			

## Units Summary

Diameter Units      Inches  
Length Units      Feet  
Flow Units      US Gallons per Minute  
Pressure Units      Pounds per Square

**Received after DRC Meeting  
to address DRC comments  
prior to the submission of a  
Building Permit Application.**

1/27/2022

Note: Fitting Legend provides equivalent pipe lengths for fittings types of various diameters. Equivalent lengths shown are standard for actual diameters of Sched 40 pipe and CFactors of 120 except as noted with \*. The fittings marked with a \* show equivalent lengths values supplied by manufacturers based on specific pipe diameters and CFactors and they require no adjustment. All values for fittings not marked with a \* will be adjusted in the calculation for CFactors of other than 120 and diameters other than Sched 40 per NFPA.

# Pressure / Flow Summary - STANDARD

SUMMERS FIRE SPRINKLERS, INC  
Bldg#1 UNIT B

Page 4  
Date

Node No.	Elevation	K-Fact	Pt Actual	Pn	Flow Actual	Density	Area	Press Req.
15	7.67	4.9	7.0	na	12.96	0.05	171	7.0
S8	8.5		6.78	na				
S7	8.5		7.09	na				
16	8.5		8.1	na				
17	8.5		8.87	na				
TOR2	8.5		10.14	na				
BOR2	-1.5		19.22	na				
2	-1.5		19.56	na				
U12	-2.5		20.02	na				
U11	-2.5		20.28	na				
U10	-2.5		21.37	na				
U9	-2.5		21.37	na				
U6	-2.5		21.38	na				
U5	-2.5		21.41	na				
U4	-2.5		21.45	na				
BK4	-2.5		21.47	na				
BK3	1.5		25.4	na				
BK2	1.5		25.44	na				
BK1	-2.5		27.19	na				
U3	-2.5		27.2	na				
U2	-2.5		27.22	na				
U1	-2.5		27.27	na				
6	-2.5		27.3	na				
7	-2.5		27.3	na				
TEST	2.6		25.13	na	5.0			
18	7.67	4.9			13.08	0.05	160	7.0
19	7.67	4.9			13.8	0.05	160	7.0
S6	8.5							
20	7.67	4.9			14.42	0.05	171	7.0
S5	8.5							

**Received after DRC Meeting  
to address DRC comments  
prior to the submission of a  
Building Permit Application.**

**1/27/2022**

The maximum velocity is 11.41 and it occurs in the pipe between nodes 17 and TOR2

# Final Calculations : Hazen-Williams

SUMMERS FIRE SPRINKLERS, INC  
Bldg#1 UNIT B

Page 5  
Date

Node1 to Node2	Elev1 Elev2	K Fact	Qa Qt	Nom Act	Fitting or Equiv Len	Pipe Ftngs Total	CFact Pf/Ft	Pt Pe Pf	*****	Notes	*****
15 to S8	7.67 8.5	4.90	12.96 12.96	1 1.101	E	3.825 3.825 4.655	150 0.0305	7.000 -0.359 0.142		Vel = 4.37	
S8 to S7	8.5 8.5		0.0 12.96	1 1.101		10.000 10.000	150 0.0305	6.783 0.0 0.305		Vel = 4.37	
S7 to 16	8.5 8.5		13.08 26.04	1.25 1.394	2E	9.523 19.230 9.523 28.753	150 0.0351	7.088 0.0 1.010		Vel = 5.47	
16 to 17	8.5 8.5		13.80 39.84	1.25 1.394		10.000 10.000	150 0.0772	8.098 0.0 0.772		Vel = 8.37	
17 to TOR2	8.5 8.5		14.42 54.26	1.25 1.394	E	4.762 4.500 4.761 9.261	150 0.1366	8.870 0.0 1.265		Vel = 11.41	
TOR2 to BOR2	8.5 -1.5		0.0 54.26	1.25 1.44	Fsp	0.0 10.000	120 0.1751	10.135 7.331 1.751		** Fixed Loss = 3 Vel = 10.66	
BOR2 to 2	-1.5 -1.5		0.0 54.26	2 2.15			120 0.0246	19.217 0.0 0.346		Vel = 4.76	
2 to U12	-1.5 -2.5		0.0 54.26	2 2.15			120 0.0250	19.563 0.433 0.025		Vel = 4.76	
U12 to U11	-2.5 -2.5		0.0 54.26	2 2.157	E	6.153 4.190 6.153 10.343	120 0.0247	20.021 0.0 0.255		Vel = 4.76	
U11 to U10	-2.5 -2.5		0.0 54.26	2 2.157	E T	6.153 25.770 12.307 18.460 44.230	120 0.0246	20.276 0.0 1.090		Vel = 4.76	
U10 to U9	-2.5 -2.5		0.0 54.26	4 4.1		1.280 1.280	120 0.0008	21.366 0.0 0.001		Vel = 1.32	
U9 to U6	-2.5 -2.5		0.0 54.26	4 4.1		7.700 7.700	120 0.0010	21.367 0.0 0.008		Vel = 1.32	
U6 to U5	-2.5 -2.5		0.0 54.26	4 4.1	E	10.928 24.150 10.928 35.078	120 0.0011	21.375 0.0 0.038		Vel = 1.32	
U5 to U4	-2.5 -2.5		0.0 54.26	4 4.1		33.860 33.860	120 0.0011	21.413 0.0 0.037		Vel = 1.32	
U4 to BK4	-2.5 -2.5		0.0 54.26	4 4.1	E	10.928 6.510 10.928 17.438	120 0.0010	21.450 0.0 0.018		Vel = 1.32	
BK4 to BK3	-2.5 1.5		0.0 54.26	4 4.1	Zaf	0.0 4.000 4.000	120 0.0012	21.468 3.927 0.005		** Fixed Loss = 5.659 Vel = 1.32	

Received after DRC Meeting  
to address DRC comments  
prior to the submission of a  
Building Permit Application.  
1/27/2022

# Final Calculations : Hazen-Williams

SUMMERS FIRE SPRINKLERS, INC  
Bldg#1 UNIT B

Page 6  
Date

Node1 to Node2	Elev1 Elev2	K Fact	Qa Qt	Nom Act	Fitting or Equiv Len	Pipe Ftngs Total	CFact Pf/Ft	Pt Pe Pf	*****	Notes	*****
BK3 to BK2	1.5 1.5		0.0 54.26	4 4.1	2E	21.855 21.855 35.015	120 0.0011	25.400 0.0 0.037		Vel = 1.32	
BK2 to BK1	1.5 -2.5		0.0 54.26	4 4.1	E	10.928 10.928 14.928	120 0.0011	25.437 1.732 0.017		Vel = 1.32	
BK1 to U3	-2.5 -2.5		0.0 54.26	4 4.1	E	14.534 14.534 19.914	140 0.0008	27.186 0.0 0.016		Vel = 1.32	
U3 to U2	-2.5 -2.5		0.0 54.26	4 4.1	E	14.534 14.534 18.344	140 0.0008	27.202 0.0 0.015		Vel = 1.32	
U2 to U1	-2.5 -2.5		0.0 54.26	4 4.1	T	29.067 29.067 61.257	140 0.0008	27.217 0.0 0.050		Vel = 1.32	
U1 to 6	-2.5 -2.5		0.0 54.26	4 4.1	2E	29.067 29.067 30.067	140 0.0008	27.267 0.0 0.034		Vel = 1.32	
6 to 7	-2.5 -2.5		0.0 54.26	4 4.1			140 0.0008	27.301 0.0 0.001		Vel = 1.32	
7 to TEST	-2.5 2.600		0.0 54.26	4 4.1			140 0.0008	27.302 -2.209 0.037		Vel = 1.32	
TEST			5.00 59.26					25.130		Qa = 5.00 K Factor = 11.82	
18 to S7	7.67 8.5	4.90	13.08	1 1.101	T	9.563 0.830 9.562 10.392	150 0.0310	7.125 -0.359 0.322		Vel = 4.41	
S7			0.0 13.08					7.088		K Factor = 4.91	
19 to S6	7.67 8.5	4.90	13.80	1 1.101	E	3.825 0.830 3.825 4.655	150 0.0342	7.931 -0.359 0.159		Vel = 4.65	
S6 to 16	8.5 8.5		0.0 13.8	1 1.101	T	9.563 1.170 9.562 10.732	150 0.0342	7.731 0.0 0.367		Vel = 4.65	
16			0.0 13.80					8.098		K Factor = 4.85	
20 to S5	7.67 8.5	4.90	14.42	1 1.101	E	3.825 0.830 3.825 4.655	150 0.0369	8.658 -0.359 0.172		Vel = 4.86	
S5 to 17	8.5 8.5		0.0 14.42	1 1.101	T	9.563 1.170 9.562 10.732	150 0.0372	8.471 0.0 0.399		Vel = 4.86	
17			0.0 14.42					8.870		K Factor = 4.84	

Received after DRC Meeting  
to address DRC comments  
prior to the submission of a  
Building Permit Application.  
1/27/2022

# Final Calculations : Hazen-Williams

SUMMERS FIRE SPRINKLERS, INC  
Bldg#1 UNIT B

Page 7  
Date

Node1	Elev1	K	Qa	Nom	Fitting or	Pipe	CFact	Pt			
to						Ftngs		Pe	*****	Notes	*****
Node2	Elev2	Fact	Qt	Act	Equiv	Len	Pf/Ft	Pf			

