DATE: 3/4/2024
REV:
BY: DJC

Pompano Beach Snack Bar

STORMWATER MANAGEMENT CALCULATIONS

PRE		
LAND USE BREAKDOWN		
LAND USE BREAKDOWN	ACRES	PERCENT %
Building	0.012	9.6%
concrete	0.041	32.1%
Green	0.074	58.3%
TOTAL	0.128	100.0%
Impervious surface	0.053	41.7%
Pervious surface	0.074	58.3%

POST		
LAND USE BREAKDOWN		
LAND USE BREAKDOWN	ACRES	PERCENT %
Building	0.035	27.3%
concrete	0.060	46.7%
Green	0.033	26.0%
TOTAL	0.128	100.0%
Impervious surface	0.094	74.0%
Pervious surface	0.033	26.0%

Water Table Elevation: **2.50** NAVD

Compute the water quality volume required based on the increas of impervious area from PRE and POST tables above:

1. Increase in impervious surface:

Proposed Impervious surface - existing impervious surface = 0.094 - 0.053

= **0.041** ac

2. Water Quality Calculations

A. Compute the first inch of runoff from the entire site.

= 1 inch x Total Area x (1 ft / 12 in)

= 0.0034 ac-ft

B. For 2.5 inches times percentage of imperviousness

= 2.5 inches x %imp

= 0.0086 inches **(CONTROLS)**

C. Volume to be treated: 0.0086 ac-ft

3. Exfiltration Trench Calculations

$L_{min} = FS*V/[K \times (H_2W + 2H_2D_u - D_u^2 + 2H_2D_s) + (1.39 \times 10^{-4})WD_u]$

= 0.52 feet

Trench Characteristics

volume, V=	0.0086	ac-ft
L=	8	used
W=	4	
K (CFS/ft^2)=	2.50E-04	
H_2=	9.00	ft
D_u=	7.50	ft
D_s=	0.00	
Top of Trench Elev.=	10.00	ft
Bottom of Trench Elev.=	2.50	ft
Rim Elev.=	11.50	ft

Martin Pilote,
Fla. PE #55992
for Globe Engineering, Inc.
4839 SW 148 Avenue, Suite 507
Fort Lauderdale, FL 33330
P: 954-316-7628
FBPE registry# 8604

Martin Pilote Digitally signed by Martin Pilote Date: 2024.03.04 09:53:55 -05'00'

MARTIN PILOTE, State of Florida, Professional Engineer, License No. 55992

This item has been digitally signed and sealed by MARTIN PILOTE on the date indicated here.

Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

DRC

PZ24-12000002
04/17/2024