



Wilkinson Hi-Rise

A WHR Holdings Company

5 7 2021

VALERIA MASTRAPA
DESIGN MANAGER



Re: HARBORSIDE AT HIDDEN HARBOUR

The residential component of the project is made up 2 building with 271 units. It will use Qty.2 waste chutes with chute feed compactors. The building is designed around the equipment and will accommodate compactor units with 2-yard compaction containers for waste. The building will be service 3 days a week for waste. Waste pick up Qty.12 2-yard containers, (See attached drawings). All waste will be consolidated at loading zones for pick up.

Commercial Waste; Will use an AccuPak Model 300 compactor for the restaurant waste. The restaurant will be service 3 days a week for waste. Waste pick up Qty.4 2-yard containers which will be moved to Marine / Retail and Showroom waste storage room during off hours using a Waste Caddy.

The above equipment will meet the city recycling ordinance as well as handle the volume of solid waste for the project. (See attached drawings).

If you have any questions or concerns, please give me a call at (954) 342-4400.

Michael F. Bracken

Michael F. Bracken
President