EXISTING TREE DISPOSITION CHART

SHOPPERS HAVEN FIRE HOUSE - Pompano Beach, FL

TREE NO.	BOTANICAL NAME	COMMON NAME	HT (ft)	SPR (ft)	DBH (ins)	CONDITION	COMMENTS	DISPOSITION	VALUE
375	*Bursera simaruba*	Gumbo Limbo	25	30	24	60%	off-site	REMAIN	$ 9,349.06
376	*Bursera simaruba*	Gumbo Limbo	18	18	8	60%		REMAIN	$ 1,421.97
377	*Conocarpus e. sericeus*	Silver Buttonwood	15	15	8	50%		REMAIN	$ 781.89
378	*Conocarpus e. sericeus*	Silver Buttonwood	12	15	12	45%		REMAIN	$ 1,518.58
379	*Cocos nucifera*	Coconut Palm	25	15	8	60%		REMAIN	$ 702.87
380	*Quercus virginiana*	Live Oak	25	20	8	70%		REMAIN	$ 3,690.05
381	*Quercus virginiana*	Live Oak	20	20	8	75%		REMAIN	$ 3,953.63
382	*Quercus virginiana*	Live Oak	30	30	16	65%		REMAIN	$ 9,057.51
383	*Quercus virginiana*	Live Oak	40	30	24	70%		REMAIN	$ 19,861.23
384	*Callistemon viminallis*	Bottlebrush	10	5	3	30%		REMAIN	$ 68.87
385	*Callistemon viminallis*	Bottlebrush	10	5	3	30%		REMAIN	$ 68.87
386	*Callistemon viminallis*	Bottlebrush	12	10	4	40%		REMAIN	$ 137.46
387	*Callistemon viminallis*	Bottlebrush	12	12	8	35%		REMAIN	$ 394.07
A	*Bursera simaruba*	Gumbo Limbo	15	15	4	40%		REMAIN	$ 453.53
B	*Bursera simaruba*	Gumbo Limbo	18	15	8	50%		REMAIN	$ 1,184.97
							TOTAL NON-SPECIMEN DBH ON SITE:		90
							TOTALSPECIMEN VALUE ON SITE:		$ 19,861.23
							TOTAL NON-SPECIMENT DBH TO REMAIN:		90
							TOTAL SPECIMEN VALUE TO REMAIN:		$ 19,861.23



NOTE: BARRIER TO FORM CONTINUOUS FROM AROUND THE TREE OR GROUP OF TREES. SEE LANDSCAPE PLAN FOR LOCATION OF TREES TO REMAIN.

LANDSCAPE STANDARDS

REVISIONS		URBAN FORESTRY	TREE PROTECTION DETAIL	
BY	DATE	CITY OF POMPANO BEACH	APPROVED BY:	DATE: APRIL 2010
TCW	APRIL2010			DWG. NO.
		SCALE: N.T.S.	URBAN FORESTER	104-1

WORK MUST BE SUPERVISED BY AN ISA CERTIFIED ARBORIST.

ROOT PRUNING MUST BE DONE A MINIMUM OF 8 WEEKS PRIOR TO RELOCATION.

WATERING MUST PROVIDE SUFFICIENT WATER TO MAINTAIN A MOIST CONDITION IN THE ROOTS. AUTOMATIC IRRIGATION DRIP IS RECOMMENDED.

TAKE EXTRA CARE NOT TO DAMAGE THE TRUNK OR BRANCHES.



LANDSCAPE STANDARDS

REVISIONS		URBAN FORESTRY	ROOT PRUNING DETAIL	
BY	DATE	CITY OF POMPANO BEACH	APPROVED BY:	DATE: AUGUST 2010
TCW	APRIL2010			DWG. NO.
		SCALE: N.T.S.	URBAN FORESTER	105-1

GENERAL NOTES:

10. Contractor is responsible for determining all utility locations and installing facilities so as to not conflict. All damage to existing utilities or improvements caused by Contractor shall be repaired at no additional cost to the Owner.

11. Contractor to notify "Sunshine State One Call of Florida, Inc." at 1-800-432-4770 Two Full Business Days prior to digging for underground utility locations.

12. Contractor shall be responsible for providing final grading of all associated planting areas.

13. After final grade, area to be raked to 6" depth and all rock and foreign inorganic materials removed and disposed of properly off-site.

29. Tree protection barricades shall be provided by Landscape Contractor around existing trees that may be impacted by the proposed construction. Prior to any construction a tree protection barricade inspection shall be conducted by the landscape architect, owner or governing municipality. Refer to landscape detail for tree preservation barricade fencing.

THOMAS ENGINEERING GROUP
CIVIL ENGINEERS - PROJECT MANAGERS - LAND PLANNING - LANDSCAPE ARCHITECTS
1000 CORPORATE DR. SUITE 250 FT. LAUDERDALE, FL 33334 P: 954-202-7000
4950 W. KENNEDY BLVD. SUITE 600 TAMPA, FL 33609 P: 813-379-4100
125 W INDIANTOWN RD. SUITE 206 JUPITER, FL 33458 P: 561-203-7903

THE INFORMATION, DESIGN, AND CONCEPTS OF THIS PLAN ARE PROPRIETARY AND SHALL NOT BE COPIED OR USED FOR ANY PURPOSE WITHOUT PRIOR WRITTEN AUTHORIZATION FROM THOMAS ENGINEERING GROUP, LLC. ONLY APPROVED, SIGNED AND SEALED PLANS SHALL BE UTILIZED FOR CONSTRUCTION. UNAUTHORIZED USE OF THESE PLANS AND/OR DESIGNS SHALL BE AT USER'S SOLE RISK AND WITHOUT LIABILITY TO THOMAS ENGINEERING GROUP, LLC.

REVISIONS:

REV:	DATE:	COMMENT:	BY:

811 KNOW WHAT'S BELOW ALWAYS CALL 811 BEFORE YOU DIG
It's fast. It's free. It's the law.
www.callsunshine.com

PROJECT No.: F170010
DRAWN BY: KB
CHECKED BY: MAT
DATE:
CAD I.D.: F170010 - LANDSCAPE PLAN- FIRE STATION

PROJECT:

SHOPPER'S HAVEN

FOR

PARTRIDGE EQUITY GROUP

POMPANO BEACH
FLORIDA

THOMAS ENGINEERING GROUP
6300 NW 31ST AVE
FORT LAUDERDALE, FL 33309
PH: (954) 202-7000
FX: (954) 202-7070
www.ThomasEngineeringGroup.com

MICHAEL D. GROSSWIRTH
LA 6666871
STATE
REGISTERED LANDSCAPE ARCHITECT
August 25, 2020
FLORIDA REGISTRATION NO. LA6666871
FLORIDA BUSINESS CERT. OF AUTH. No. 27528

SHEET TITLE:

TREE DISPOSITION CHART, NOTES & DETAILS

SHEET NUMBER:

L-1.1

DRC
PZ20-05000004
10/21/20

Plotted: Monday, August 24, 2020, 9:51 AM by Michael Grosswirth
G:\PROJECTS\2017\F170010 - SHOPPERS HAVEN FIRE STATION\LANDSCAPE\PLAN ENTITLEMENTS - PRE STATION\LANDSCAPE\F170010 - LANDSCAPE PLAN- FIRE STATION.dwg - LAYOUT: L-1.1

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MICHAEL D. GROSSWIRTH, LA6666871 ON 2020-08-25