

WOOD DOCK IDENTIFICATION:

- 1. NEW 10" Ø WOOD PILINGS (17 TOTAL 8 CUT BELOW DECK)
- 2. 2" X 8" SUBSTRINGER WITH (1) 5/8" THRU BOLT OR LAG BOLT @ PILINGS AND HANGERS
- 3. (2) 2" X 8" STRINGERS @ PILINGS WITH (1) 5/8" THRU BOLT OR LAG BOLT TO PILINGS
- 4. 2" X 8" STRINGERS W/ (2) 16D NAILS TO EACH SUBSTRINGER; @ 16"O.C. FOR AZEK DECK BOARDS OR 24"O.C. FOR PRESSURE TREATED WOOD DECKBOARDS OR 5/4" IPE DECK BOARDS
- 5. 5" X 5" HANGER WITH (1) 5/8" THRU BOLT OR LAG BOLT TO SUBSTRINGER
- 6. PROPOSED HDPE DECKING WITH S.S. DECK SCREWS
- 7. 2" X 8" FASCIA BOARD
- 8. 2" X 4" WOOD TRIM

PREPARED FOR:

B&M MARINE CONSTRUCTION, INC. 1211 S. MILITARY TRAIL SUITE #200 DEERFIELD BEACH, FL 33442 O: (954) 421 - 1700

PROJECT:

SHEET 3 OF 5

New Wood Dock for Vincenzo Costanza 777 South Federal Hwy C-203 Pompano Beach, FL 33062 MARK WEBER, P.E. LICENSE #53895 CA30702

MW ENGINEERING, INC.

902 NE 1ST STREET SUITE #2 POMPANO BEACH, FLORIDA 33060 OFFICE: (754) 333 - 0877 WEBSITE: MWENGINEERING.NET