




SW 2ND ST



SECTION 2 TOWNSHIP 49S RANGE 42E  
Permit Set, Not for Construction/Bidding



CLEARING/ EROSION PLAN NOTES

1. ALL CONSTRUCTION BARRICADES AND SILT FENCES WILL REMAIN IN PLACE AND BE MONITORED FOR COMPLIANCE BY THE PERMIT HOLDER DURING THE PERMITTED DEVELOPMENT ACTIVITIES.
2. SOIL STABILIZATION SHALL BE COMPLETED WITHIN 30 DAYS OF VEGETATION REMOVAL.
3. CLEARED LAND WITH NO CONSTRUCTION ACTIVITY WITHIN 30 DAYS SHALL BE SEEDED AND MULCHED.
4. NO CLEARING SHALL TAKE PLACE BEYOND SILT FENCE.
5. FILTER FABRIC SHALL BE INSTALLED UNDER INLET GRATES. FABRIC SHALL NOT BE REMOVED UNTIL ALL LANDSCAPING AND SOD IS INSTALLED.
6. MINIMUM 12" DEEP #4 FDOT AGGREGATE SHALL BE INSTALLED AT THE CONSTRUCTION ENTRANCE PRIOR TO START OF CONSTRUCTION.
7. PLEASE SEE SHEET C-11 FOR DETAILS ON SILT FENCE AND EROSION CONTROL DEVICES FOR CATCH BASINS, TURBIDITY BARRIER AND CONSTRUCTION ENTRANCE SILT FENCE SHALL BE INSTALLED AT PROPERTY LINE.
9. CONTRACTOR TO FOLLOW ALL FDEP NPDES, LOCAL AND OTHER STATE REQUIREMENTS FOR POLLUTION PREVENT AND EROSION CONTROL ONCE CONSTRUCTION COMMENCES.

LEGEND	
000.0	PROP PAVT EL
00.0	PROP CONC SW EL
EXIST	EXIST EL
CONTRACTOR TO FIELD VERIFY	CONTRACTOR TO FIELD VERIFY
INVERT EL	INVERT EL
CATCH BASIN	CATCH BASIN
YARD DRAIN	YARD DRAIN
BOTTOM EL	BOTTOM EL
TOP EL	TOP EL
EXF	EXFILTRATION TRENCH
WM	WATER MAIN
WS	WATER SERVICE
FM	FIRE MAIN
FM	FIRE MAIN
UCW	UNDERGROUND WIRE
STM	STORM LINE
WW	WASTEWATER GRAVITY
PIV	POST INDICATOR VALVE
GV	GATE VALVE
TV	TAPPING VALVE
VALVE	VALVE
CV	CY CHECK VALVE
DDDA=DDL OHK DETECTOR ASSEMBLY	DDDA=DDL OHK DETECTOR ASSEMBLY
RPDA=REDUCED PRESS DET ASSEMBLY	RPDA=REDUCED PRESS DET ASSEMBLY
WATER METER W/ REDUCED PRESSURE BACKFLOW PREV	WATER METER W/ REDUCED PRESSURE BACKFLOW PREV
SAMPLE POINT	SAMPLE POINT
MES	METERED END SECTION
F.F.E.L	FIN FLOOR ELEV
F.L.E.L	FLOW LINE ELEV
TOB	TOP OF BANK
TOS	TOP OF SLOPE
TC	TOP OF CONCRETE
TP	TOP OF PAVEMENT
UE	UTILITY EASEMENT
DE	DRAINAGE EASEMENT
LINE	LINE MAINTENANCE EASMT
LAT	LIMITED ACCESS EASMT
CO	CLEANOUT
BORING NO. AND LOCATION	BORING NO. AND LOCATION
ERCP	ELLIPITICAL RCP
RCP	REINFORCED CONC PIPE
CAP	CORRUGATED ALUMINUM PIPE
HDPE	HIGH DENSITY POLYETHYLENE PIPE
PVC	POLYVINYL PIPE
OMP	CORRUGATED METAL PIPE
CONC	PROP CONC EL

48 HOURS BEFORE BEGINNING  
CALL TOLL FREE  
811  
CALL SURFACE  
NOTIFICATION CENTER  
3/26/2025

REVISIONS			
10/14/24	REV	PER	SP-DRC
12/19/24	REV	PER	SP-DRC

**Jeff H. Iravani, Inc.**  
Consulting Engineers

1934 COMMERCE LANE, SUITE 5  
JUPITER, FLORIDA 33458  
TEL: (561) 575-6030  
FAX: (561) 575-6088  
www.JHinc.com

201 SW 12th Ave  
Pompano Beach, Florida

Erosional Control & Pollution Prevention Plan		JOB NO.
DATE	SCALE	1"=20'
DESIGNED BY	DRAWN BY	JBI
08/05/2022	2208-1411	

SEAL  
CDA # 6986  
SHEET NO.  
C-5