



PAVEMENT NOTES:

1. THE WEARING SURFACE SHALL BE INSTALLED IN TWO LIFTS. THE FIRST LIFT SHALL BE 3/4" OF TYPE SP9.5 MOD. ASPHALTIC CONCRETE OVER PRIME COAT AND SAND SEAL. THE SECOND LIFT SHALL BE 3/4" OF TYPE SP9.5 MOD. ASPHALTIC CONCRETE (APPLY TACK COAT BETWEEN LIFTS).
2. THE BASE COURSE SHALL BE LIMEROCK (70% CALCIUM MIN.) CONSTRUCTED TO THE THICKNESS INDICATED AND SHALL HAVE A MINIMUM LBR OF 100. THE BASE MATERIAL SHALL BE COMPACTED TO A DENSITY OF NOT LESS THAN 98% OF MAXIMUM DENSITY AS DETERMINED BY KASHTO T-180. PRIME COAT SHALL BE APPLIED AT A RATE OF 0.25 GALLONS PER SQUARE YARD. PRIME AND TRACT COAT FOR BASE SHALL CONFORM TO THE REQUIREMENTS AND SPECIFICATIONS OF SECTIONS 300-1 THROUGH 300-7 OF F.D.O.T. STANDARDS SPECIFICATION.
3. ALL ORGANIC AND YIELDING MATERIAL SHOWN SHALL BE REMOVED AND REPLACED WITH GLEAN FILL. THE SUB-BASE SHALL EXTEND 12" BELOW THE BASE COURSE, SHALL HAVE A MINIMUM LBR OF 40 AND SHALL BE COMPACTED TO 100% OF MAXIMUM DRY DENSITY AS PER KASHTO T-180.

NOTE:  
ALL ELEVATIONS REFER TO NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD-88).

NO.	REVISIONS	DATE

CONCEPTUAL GRADING & DRAINAGE SECTIONS			
PALM AIRE TENNIS CENTER			
RW 7' EXPOSED ASPHALT PAVEMENT			
WINNIFRAM FADLEY ENGINEERS & SURVEYORS 11 N.E. 4th Street, Suite 200, Oakland Park, FL 33334 407.771.7440 (F) 407.771.7441 (C) www.winnifram.com			
DESIGNED: AMF/BMP	DATE: 01/20/23	PROJECT NUMBER: 44049	SHEET: 1
DRAWN: AMF	DATE: 01/20/23	PROJECT NUMBER: 44049	SHEET: 1
CHECKED: BMP	DATE: 01/20/23	PROJECT NUMBER: 44049	SHEET: 1

06/21/2023