
[illegible]

1. SEDIMENT BASINS AND TRAPS, PERMITTER DICES, SEDIMENT BARRIERS AND OTHER MEASURES INTENDED TO TRAP SEDIMENT SHALL BE CONSTRUCTED AS A FIRST STEP IN ANY LAND DISTURBING ACTIVITY AND SHALL BE MADE FUNCTIONAL BEFORE UP-SLOPE LAND DISTURBANCE TIMES.
2. ALL SEDIMENT CONTROL MEASURES ARE TO BE ADJUSTED TO MEET FIELD CONDITIONS AT THE TIME OF CONSTRUCTION AND BE CONSTRUCTED PRIOR TO ANY GRADING OR DISTURBANCE OF EXISTING SURFACE MATERIAL ON BALANCE OF SITE. PERMITTER SEDIMENT BARRIERS SHALL BE CONSTRUCTED TO PREVENT SEDIMENT OR TRASH FROM FLOWING OR FLOATING ON TO ADJACENT PROPERTIES.
3. PERMANENT OR TEMPORARY SOIL STABILIZATION SHALL BE APPLIED TO DENUDED AREAS WITHIN SEVEN (7) DAYS AFTER FINAL GRADE IS REACHED ON ANY GRADING OR DISTURBANCE OF EXISTING SURFACE MATERIAL. STABILIZATION SHALL BE APPLIED WITHIN SEVEN (7) DAYS TO DENUDED AREAS THAT ARE NOT TO BE AT FINAL GRADE BUT WILL REMAIN UNDISTURBED FOR LONGER THAN 30 DAYS. PERMANENT STABILIZATION SHALL BE APPLIED TO AREAS THAT ARE TO BE LEFT UNDISTURBED FOR MORE THAN ONE YEAR.
4. DURING CONSTRUCTION OF THE PROJECT, SOIL STOCK PILES SHALL BE PROTECTED, COVERED OR CONTAINED WITH SEDIMENT TRAPPING MEASURES. IF THE APPLICANT IS RESPONSIBLE FOR CONSTRUCTION AND PERMANENT STABILIZATION OF ALL SOIL STOCKPILES ON SITE AS WELL AS SOIL INTENTIONALLY TRANSPORTED FROM THE PROJECT SITE.
5. A PERMANENT VEGETATIVE COVER SHALL BE ESTABLISHED ON DENUDED AREAS NOT OTHERWISE PERMANENTLY STABILIZED.
6. AFTER ANY SIGNIFICANT RAINFALL, SEDIMENT CONTROL STRUCTURES WILL BE INSPECTED FOR INTEGRITY. ANY DAMAGED DEVICES SHALL BE CORRECTED IMMEDIATELY.
7. CONCENTRATED RUNOFF SHALL NOT FLOW DOWN CUT OR FILL SLOPES UNLESS CONTAINED WITHIN AN ADEQUATE TEMPORARY OR PERMANENT CHANNEL, FLUME, SLOPE DRAIN STRUCTURE OR APPROVED CONTROL.
8. SEDIMENT WILL BE PREVENTED FROM ENTERING ANY STORM WATER SYSTEM, DITCH OR CHANNEL. ALL STORM WATER INLETS THAT ARE MADE PERMEABLE DURING CONSTRUCTION SHALL BE PROTECTED. SEDIMENT-LOADED WATER CANNOT ENTER THE CONVEYANCE SYSTEM WITHOUT FIRST BEING FILTERED OR OTHERWISE TREATED TO REMOVE SEDIMENT.
9. WHEN WORK IN A LIVE WATERCOURSE IS PERFORMED, PRECAUTIONS SHALL BE TAKEN TO MINIMIZE ENDOCRINOLOGICAL, CULTURAL, SEDIMENT TRANSPORT AND STABILIZE THE WORK AREA TO THE GREATEST EXTENT POSSIBLE DURING CONSTRUCTION.
10. DURING INSPECTION OF ALL SEDIMENT CONTROL STRUCTURES MUST BE PROVIDED TO ENSURE INTENDED PURPOSE IS ACCOMPLISHED. THE DEVELOPER, OWNER AND/OR CONTRACTOR SHALL BE CONTINUALLY RESPONSIBLE FOR ALL SEDIMENT CONTROLS. SEDIMENT CONTROL MEASURES SHALL BE IN WORKING CONDITION AT THE END OF EACH WORKING DAY.
11. WHERE CONSTRUCTION VEHICLE ACCESS ROUTES INTERSECT PAVED PUBLIC ROADS, PROVISIONS SHALL BE MADE TO MINIMIZE THE TRANSPORT OF SEDIMENT BY TRACKING INTO THE PAVED SURFACE. SEDIMENT SHALL BE TRANSPORTED OVER A PUBLIC ROAD SURFACE WITH CURBS AND GUTTERS. OFF-ROAD ROAD SHALL BE CLOSURE AT THE END OF EACH WORKING DAY. SEDIMENT SHALL BE REMOVED FROM THE ROADS BY SHOVELING OR SWEEPING AND TRANSPORTED TO A SEDIMENT CONTROL DISPOSAL AREA. STREET WASHING SHALL BE ALLOWED ONLY AFTER SEDIMENT IS REMOVED IN THIS MANNER. THIS PROVISION SHALL APPLY TO INDIVIDUAL SUBURBION LOTS AS WELL AS TO LARGER LAND DISTURBING ACTIVITIES.
12. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION OR AFTER THE TEMPORARY MEASURES ARE NO LONGER NEEDED.
13. PROPERTIES AND WATERWAYS DOWNSTREAM FROM CONSTRUCTION SITES SHALL BE PROTECTED FROM SEDIMENT DEPOSITION AND EROSION AT ALL TIMES DURING CONSTRUCTION.
14. THE CONTRACTOR IS RESPONSIBLE FOR ALL SURFACE WATER DISCHARGES, RAINFALL RUN OFF OR DRAINAGE ACTIVITIES.
15. CONTRACTOR MUST INCORPORATE ALL BMP'S NECESSARY TO MEET OR EXCEED STATE WATER QUALITY AND SWPPP REQUIREMENTS.
16. THE POLLUTION PREVENTION PLAN IS A MINIMUM GUIDELINE ONLY. ADDITIONAL BMP'S MAY BE NECESSARY AT CONTRACTOR'S EXPENSE.
17. NOI SHALL BE POSTED ON SITE.
18. DRAINING ACTIVITIES:
  - a. DISCHARGE MUST NOT EXCEED STATE WATER QUALITY STANDARDS.
  - b. CONTRACTOR MUST HAVE A TRANSFERABLE SWMD DRAINING PERMIT.
  - c. NO HYDRAULIC PUMPS MAY BE USED FOR DRAINING UNLESS APPROVED BY THE WATER MANAGEMENT DISTRICT FOR THAT AREA.

**PHASING NOTES:**

1. CONTRACTOR MAY PHASE EROSION AND SEDIMENTATION CONTROL MEASURES IN ACCORDANCE WITH SITE CONSTRUCTION PHASING.
2. CONTRACTOR SHALL ENSURE THAT THE CONSTRUCTION AREA IS SEPARATED FROM THE AREA NOT UNDER CONSTRUCTION WITH A TEMPORARY CHAIN LINK FENCE AND ENSURE THE SAFETY OF THE PUBLIC.
3. CONTRACTOR SHALL PROVIDE SWPPP AS REQUIRED FOR THE PROPOSED PAVING, GRADING AND DRAINAGE PLAN. SEE ATTACHED DETAILS AS NECESSARY.

 <div style="margin-left: 20px;"> <b>DYNAMIC</b>          ENGINEERING • SURVEY          TRAFFIC       </div>	
<p style="text-align: center;"><b>THIS PLAN SET IS FOR PERMITTING PURPOSES ONLY AND MAY NOT BE USED FOR CONSTRUCTION</b></p>	<div style="display: flex; justify-content: space-between;"> <div style="width: 45%;">           DRAWN BY: _____             DESIGNED BY: _____             SRM _____ EC _____         </div> <div style="width: 45%;">           CHECKED BY: _____             AP _____         </div> </div>
<p style="text-align: center;">PROJECT: <b>LT 20, LLC</b>  <b>PROPOSED WAREHOUSE ADDITION</b>          PARCEL ID# 4842-26-00-0371          115 NW 16TH STREET          POMPANO BEACH, BROWARD COUNTY, FL 33060</p>	


  

<h2 style="margin: 0;">DYNAMIC ENGINEERING</h2> <p style="font-size: small; margin: 0;">LAND DEVELOPMENT CONSULTING • PERMITTING GEOTECHNICAL • ENVIRONMENTAL TRAFFIC • SURVEY • PLANNING &amp; ZONING</p> <p style="margin-top: 10px;">100 NE 5th Avenue Suite 52 Delray Beach, FL 33483 T: 561.921.8570</p> <p style="font-size: x-small; margin: 0;">Offices conveniently located throughout the United States:          New Jersey   Delaware   Florida   Maryland   Pennsylvania   Texas  <u>Florida Certificate of Authorization No. 32353</u></p> <p style="text-align: center; font-weight: bold; margin-top: 10px;">www.dynamiccec.com</p>	
---	--

<h1 style="margin: 0;">ÁNGEL PIÑERO</h1> <hr style="width: 50%; margin: 10px auto;"/> <p style="text-align: center; font-weight: bold; font-size: small;">PROFESSIONAL ENGINEER</p> <p style="text-align: center; font-weight: bold; font-size: x-small;">FLORIDA LICENSE NO. 88047</p> <p style="text-align: center; font-weight: bold; font-size: x-small;">DATE:</p>
---

 <p style="font-size: x-small; margin: 0;">Know what's below Call before you dig.</p>	<p style="text-align: center; font-weight: bold; font-size: small;">PROTECT YOURSELF</p> <p style="font-size: x-small; margin: 0;">ALL STATES REQUIRE NOTIFICATION OF ENGINEERS, DESIGNERS, OR ANY PERSON PREPARING TO DISRUPT THE EARTH'S SURFACE ANSWERS IN ANY STATE</p> <p style="font-weight: bold; font-size: small;">FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM</p>
--	--

<p>TITLE: <b>DEMOLITION &amp; EROSION CONTROL PLAN – PHASE I</b></p>	
<p>SCALE: (H) AS NOTED</p> <p>PROJECT No: 5758-25-01613</p>	<p>DATE: 04/15/2025</p>

<p>SHEET No: <b>C2.00</b></p>	<p>Rev. #: <b>2</b></p>
-------------------------------	-------------------------