

PZ23-12000001
05/03/2023




1. ALL METERS WILL BE SUPPLIED AND INSTALLED BY COPB UTILITIES. METER HAS IRON PIPE THREAD MALE CONNECTION ON EACH END.
2. METER SHALL BE CENTERED IN BOX.
3. DUAL CHECK IS SAME SIZE AS CUSTOMER'S SERVICE LINE.

METER SIZE	LAYING LENGTH (IN)	HEIGHT (IN)
5/8"	7.5	4.56
1"	10.75	5.75

METER BOX INSTALLATION

ENGINEERING STANDARDS 2018			
REVISIONS		ENGINEERING DIVISION CITY OF POMPAÑO BEACH	METER BOX INSTALLATION FOR 5/8" AND 1" METERS
BY	DATE		
S.S.	11-2012		
		SCALE: N.T.S.	DATE: JAN. 2012 DWG. NO. 105-2



ENGINEERING STANDARDS 2018

REVISIONS		ENGINEERING DIVISION CITY OF POMPANO BEACH	SERVICE LATERALS	
BY	DATE			DATE: JUNE 1996 DWG. NO. 200-1
T.W.	11-2007			
S.S.	01/27/12			
S.S.	07/10/12			
S.S.	02/05/16			
SCALE: N.T.S.				


WATER AND SEWER DETAILS

ATLANTIC ENGINEERING SERVICES, INC.

2822 WATERS EDGE CIRCLE
GREENACRES, FLORIDA 33413
PHONE - (561) 358-4140
FAX - (561) 966-9242
CERTIFICATE OF AUTHORIZATION NO.: 9390

CERTIFICATE OF AUTHORIZATION NO.: 9390

PROJ. NO. 0001
SCALE: 1"=10'



PZ23-12000001
03/01/2023

REV.	DESCRIPTION	DATE
1		
2		
3		
4		
5		
6		

IMTIAZ AHMED, P.E.
LICENSED ENGINEER NO. 46102
STATE OF FLORIDA

Digitally signed
by Imtiaz
Ahmed
Date:
2023.01.17
10:18:11 -05'00'

SEAL

NEW 3 UNIT RESIDENCE
1300 N. RIVERSIDE DR
POMPAHO BEACH, FLORIDA