

PROPOSED EROSION CONTROL LEGEND

- TEMPORARY 6 FT. CHAIN LINK FENCE WITH WIND SCREEN ALONG WITH SILT FENCE.
- TEMPORARY CONSTRUCTION ENTRANCE AND WASH DOWN AREA

- NOTES:
- 1.) CONTRACTOR SHALL ASSUME ANY AND ALL RESPONSIBILITIES FOR ANY WATER CONTROL VIOLATIONS RESULTING FROM FAILURE TO ELIMINATE AND/OR CONTROL TURBID RUNOFF FROM LEAVING THE SITE AS ISSUED BY ANY AGENCY HAVING JURISDICTION.
 - 2.) CONTRACTOR SHALL PROVIDE TEMPORARY DEWATERING AREA(S) PRIOR TO ANY EXCAVATION FOR PIPE INSTALLATION. DEWATERING AREA(S) SHALL BE PROTECTED WITH SILT SCREENS. ALL DEWATERING OPERATIONS SHALL DISCHARGE INTO TEMPORARY DEWATERING AREA(S) AND NO DIRECT DISCHARGE INTO THE EXISTING OR NEW DITCHES, STORM DRAINS, AND/OR PUBLIC RIGHT OF WAY WILL BE ALLOWED.
 - 3.) CONTRACTOR SHALL MAINTAIN A POLLUTION PREVENTION CONTROL LOG AND CONDUCT WEEKLY INSPECTIONS AND WITHIN 24 HOURS OF A 0.25" STORM EVENT.
 - 4.) CONTRACTOR TO EMPLOY BEST MANAGEMENT PRACTICES THROUGHOUT CONSTRUCTION IN ORDER TO ENSURE POLLUTION PREVENTION. CONTRACTOR TO COMPLY WITH ALL LOCAL, STATE, AND OTHER LOCAL GOVERNMENTAL ENVIRONMENTAL REGULATIONS THROUGHOUT CONSTRUCTION.
 - 5.) DURING CONSTRUCTION, ALL CATCH BASINS TO BE EQUIPPED WITH FILTER FABRIC AND HAY BALES OVER GRATES.
 - 6.) ALL AREAS DISTURBED DURING CONSTRUCTION SHALL BE STABILIZED WITHIN A REASONABLE PERIOD OF TIME TO ASSURE MINIMUM EROSION OF SOILS.
 - 7.) NO LAND CLEARING OR GRADING SHALL BEGIN UNTIL ALL EROSION CONTROL MEASURES HAVE BEEN INSTALLED.
 - 8.) ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED IF DEEMED NECESSARY. ADDITIONAL CONTROL MEASURES SHALL BE INSTALLED AT CONTRACTORS EXPENSE.
 - 9.) ALL EXISTING STORM DRAINAGE PIPING AND STRUCTURES SHOWN ON THIS PLAN TO BE CLEANED AND TV.

ALL ELEVATIONS SHOWN ARE IN NAVD 1988 DATUM

DATUM CONVERSION
NGVD 1929 = (NAVD 1988 + 1.51')

OWNER | DEVELOPER:



DESIGN + BUILD CONTRACTOR:



DESIGN CONSULTANT:




ARCHITECT OF RECORD:

RUBEN J. PUJOL

ARCHITECT
A.I.A. AR#0010458 N.A.C.A.
12237 SW 204 TER
MIAMI, FL 33177
PH: (305)968-2155

SIGN AND SEAL:



Digitally signed
by Fabio J
Delgado De
Michele
Date:
2023.06.16
18:22:12 -04'00'

REVISIONS/COMMENTS:

PROJECT:

324 HAUS
MIXED USE | FLEX BUILDING
324 NW 6TH STREET
POMPAHO BEACH, FL 33060

PROJECT NO.: 22-031

DRAWN BY:

DATE: JULY-2022

SHEET NAME:

EROSION
CONTROL PLAN

SHEET NUMBER:

DRC
C-14
PZ22-12000032
07/19/2023

EROSION CONTROL PLAN
SCALE: 3/32" = 1'-0"