

**Exhibit "B"**

Vincent G. Burkhardt  
President



June 9, 2017

Mr. Horacio Danovich, CIP Engineer  
City of Pompano Beach  
100 West Atlantic Blvd., Suite #276  
Pompano Beach, FL 33060

RE: GMP Design-Build for the Atlantic Blvd. Bridge Improvements

Dear Mr. Danovich,

Burkhardt Construction, Inc. was asked by the ECRA to provide a Guaranteed Maximum Price (GMP) for the design-build improvements for the Atlantic Blvd. Bridge. This estimate is based on order of priority outlined by the ECRA.


This GMP is based on a 100% permitted design documents provided by Currie Sowards Aguila, Architects. The breakdowns of scopes of work are attached (Exhibit "A").

The GMP includes the following scopes of work to be performed: maintenance of traffic, clearing/demolition, earthwork/grading, roadway construction, railing removal and installation, tender house enhancements, replacement of bridge lighting, sail features, decorative low voltage lighting, mountable graphics, decorative esplanade/promenade, and landscaping/irrigation, per attached Exhibit "A".

MAINTENANCE OF TRAFFIC	\$ 290,000.00
DEMOLITION CLEARING & GRUBBING	\$ 244,325.00
EARTHWORK & GRADING	\$ 186,000.00
BRIDGE RAILING REPLACEMENT	\$ 477,135.00
TENDER HOUSE ENHANCEMENTS	\$ 240,000.00
ELECTRICAL/LIGHTING	\$ 615,000.00
TENSILE STRUCTURE SAILS	\$ 1,257,000.00

PROMENADE (EAST AND WEST SIDES OF BRIDGE)	\$ 767,000.00
MOUNTABLE GRAPHICS (NAUTICAL THEMED MURAL)	\$ 511,500.00
LANDSCAPING	\$ 40,000.00
IRRIGATION	\$ 25,900.00
<b>Guaranteed Maximum Price (GMP)</b>	<b>\$ 4,653,860.00</b>
OWNERS CONTINGENCY	<u>\$ 345,000.00</u>
TOTAL BUDGET	\$ 4,998,860.00

Sincerely,  
Burkhardt Construction, Inc.

  
Marc R. Kleisley  
Vice President

Exclusions and Clarifications

June 9, 2017

100% Permitted GMP for Design-Build for the Atlantic Blvd. Bridge Improvements

1. GMP does not include any relocation or undergrounding of any third party utilities.
2. GMP based on current site conditions.
3. GMP does not include any costs for removal / remediation of asbestos cement pipe or any other hazardous materials.
4. GMP is based on attached plan log.
5. GMP does not include any design, engineering or installation fees which may be charged to the Owner by franchise utility companies (electric, telephone, cable tv, gas, etc.).
6. GMP does not include cost of permit fees, capital improvement fees, connection fees or impact fees.
7. No undergrounding of franchise utilities is anticipated for this project.
8. GMP does not include premium time/overtime work hours.
9. GMP does not include additional insurance premium for naming individual property owners as "additional insured".
10. GMP includes all sales tax on materials.
11. The tensile structure sail auger piles is based on the assumption from the original soils report. This estimate does not include removal or replacement of any unsuitable subsoils or unforeseen subsurface conditions.
12. GMP does not include removal/replacement/modification of any traffic signalization or pedestrian signals.
13. GMP includes demolition of existing buildings but does not include any asbestos removal.
14. GMP includes a 7% Owner's Contingency.
15. GMP does not include obtaining any easements and/or property agreements or permissions needed for construction work and equipment.

# City of Pompano Beach

## Atlantic Blvd. Bridge Improvements

### DIRECT CONSTRUCTION COSTS

100% Permit set of construction documents BCI Rec'd date 6.5.17

Prepared by Burkhardt Construction, Inc.

Item Description	Quantity	U/M	Amount
<b>MAINTENANCE OF TRAFFIC</b>	1	LS	\$290,000.00
MOT PLAN			
WORK ZONE SIGNS			
BARRICADE TEMP. TYPE I, II, VP & DRUM			
BARRICADE TEMP. TYPE III, 6'			
ADVANCE WARNING ARROW PANEL			
CONES			
STEADY BURN &/OR FLASHING LIGHTS			
HI INTENSITY FLASHING LIGHT, TEMP. TYPE "B"			
VARIABLE MESSAGE BOARD			
POST MOUNTING FOR ADVANCE WARNING SIGNS			
SALES TAX FOR MOT DEVICES			
ORANGE SAFETY FENCE AND POSTS			
MOT / SAFETY DEVICE SET-UP & MAINTENANCE			
TEMPORARY PEDESTRIAN BOARDWALKS			
CONTINUOUS SITE CLEANING / DEBRIS REMOVAL			
DANGER RIBBON			
ROADWAY FLAGMEN			
TEMPORARY ASPHALT MILLINGS			
ALLOWANCE FOR SPECIALTY SIGNAGE			
CONCRETE BARRIER WALL			
TEMPORARY PEDESTRIAN BARRICADES WITH SCREEN			
ROADWAY STEEL PLATES			
TEMPORARY ROADWAY STRIPING			
LIGHT BANKS FOR NIGHT WORK			
OFF DUTY POLICE OFFICERS			
TEMPORARY STREET LIGHTING			
	NOT INCLUDED		
	NOT INCLUDED		
	NOT INCLUDED		
			\$244,325.00
<b>DEMOLITION CLEARING &amp; GRUBBING</b>			
NPDES	1	LS	
SILT FENCE	1000	LF	
TURBIDITY BARRIER	385	LF	
EXISTING TREE PROECTION	1	LS	
EXISTING TREE DEMOLITION	4	EA	
DEMO EXISTING JERSEY BARRIER BRIDGE RAILING	401	LF	
DEMO EXISTING CONCRETE RAIL AT APPROACH SLABS (4 QUADRANTS)	80	LF	
DEMO EXISTING CONCRETE TRANSITION BARRIER WALLS (N.E. BRIDGE QUADRANT)	100	LF	
DEMO EXISTING CONCRETE TRANSITION BARRIER WALLS (S.W. BRIDGE QUADRANT)	80	LF	
DEMO FOR TENDER HOUSE	1	LS	
DEMO FOR PROMENADE	1	LS	
DEMO OF MOUNTABLE GRAPHICS	1	LS	
ROLL OFF DUMPSTER	12	PUL	
			\$186,000.00
<b>EARTHWORK &amp; GRADING</b>			
ROUGH GRADE/STRIP GRASS FOR PROMENADE (EAST/WEST SIDES OF BRIDGE)	12938	SF	
SIDEWALK GRADING	366	SY	
EXCAVATE/GRADE STEPPED AND COUNTERWEIGHT FOOTINGS	110	SY	
EXCAVATE/GRADE FOR RETAINING WALL	140	SY	
EXCAVATE/ GRADE FOR LANDSCAPE AREAS (12" THICK)	949	SY	
12" COMPACTED SUBGRADE	585	SY	
TENSILE SHADE STRUCTURE SITE EARTHWORK	1	LS	
PROMENADE SITE EARTHWORK	1	LS	
FILL MANAGEMENT	1	LS	
FINAL DRESSING AND CONSTRUCTION CLEAN	1	LS	

Item Description	Quantity	U/M	Amount
<b>WATER, SEWER, DRAINAGE, AND FRANCHISE UTILITIES (N.I.C.) - ALL TO REMAIN IN EXISTING AREAS</b>			
<b>BRIDGE RAILING REPLACEMENT</b>			\$477,135.00
MAINTAIN EXISTING DRAINAGE (S.W. INLET MODIFICATION)	1	LS	
NEW WYOMING BARRIER (HOT DIPPED GALV. FINISH)	401	LF	
NEW CONCRETE BARRIER FLARES/APPROACH CONCRETE TRAFFIC RAILINGS	260	LF	
EXISTING SIDEWALK CONCRETE RESTORATION	1600	SF	
EXISTING SIDEWALK PAVER RESTORATION	550	SF	
<b>TENDER HOUSE ENHANCEMENTS</b>			\$240,000.00
MISC. CONCRETE & REBAR	1	LS	
MISC. MASONRY REPAIRS	1	LS	
MISC. METALS, (Weathervane)	1	LS	
CARPENTRY	1	LS	
METAL ROOF	1	LS	
DOORS & FRAMES EXTERIOR	1	LS	
LOUVERS	1	LS	
METAL FRAMING, DRYWALL & INSULATION	1	LS	
STUCCO & LATH; New, Patch & Repair	1	LS	
PAINTING	1	LS	
MISC. M.E.P.	1	LS	
MAINTAIN DAILY BRIDGE OPERATIONS (ALLOWANCE)	90	DAY	
<b>ELECTRICAL/ LIGHTING</b>			\$615,000.00
REPLACEMENT OF BRIDGE STREET LIGHT POLES/FIXTURES USING EX. BASES	5	EA	
SITE ELECTRIC FOR TENDER HOUSE	1	LS	
COMPUTER OPERATED LIGHTING OF TENSILE STRUCTURES USING FLOOD LIGHTS TYPE 'SA'	4	EA	
LIGHT BOLLARDS TYPE 'SD' (PROMENADE)	62	EA	
LED GRAZE LT. TYPE 'SB' (PROMENADE)	396	LF	
NEW CONT. LED GRAZE LT. TYPE 'SB1' (PROMENADE)	184	LF	
NEW LED FLOOD LIGHT TYPE 'SC' (PROMENADE)	6	EA	
NEW LED FLOOD LIGHT TYPE 'SE' (PROMENADE)	6	EA	
SERVICE POINTS COMPLETE	2	EA	
MAINTAIN EXISTING ELECTRICAL OPERATIONS AT ALL TIMES	1	LS	
<b>TENSILE STRUCTURE SAILS</b>			\$1,257,000.00
PILE TESTING AND FIELD OBSERVATION/CERTIFICATION	1	LS	
AUGER PILE CAPS	20	EA	
AUGAR PILE FOUNDATIONS	4	SETS	
NEW TENSILE STRUCTURE, POSTS, TIE-DOWNS, AND FABRIC COMPLETE	4	EA	
<b>PROMENADE (EAST AND WEST SIDES OF BRIDGE)</b>			\$767,000.00
REPLACE RIPRAP	1	LS	
GROUTING BEHIND EXISTING SEAWALL CAP	1	LS	
MISC. CONCRETE & REBAR	1	LS	
RETAINING WALL	419	LF	
NEW CONCRETE STEP FOOTING	1	LF	
NEW COUNTERWEIGHT SLAB	105	LF	
NEW CANTILEVERED CONCRETE WALK	105	LF	
NEW MASONRY WALL	136	LF	
NEW CONCRETE BEAM	136	LF	
MISC. SLAB REPAIR	1	LS	
4" CONCRETE SIDEWALKS (BROOM FINISH) W/ 12" THICKENED EDGE	2175	SF	
BROADCAST DEC. AGG. CONCRETE INCLUDING CANTILEVERED TOPPING	1464	SF	
NEW 1.5" PRECAST CONCRETE DEC. PANEL	754	SF	
PRE CAST CONCRETE SEAT CAP ON RETAINING WALL	119	LF	
MISC. CONCRETE CUTTING	1	LS	
SS CABLE RAILING	131	LF	
SS SKATE STOPS	15	EA	
ALUMINUM FABRICATION (ANIMAL SCREEN)	1	LS	
ROUGH CARPENTRY	1	LS	
CAULKING	1	LS	
DOORS & FRAMES EXTERIOR FOR NEW ELECTRICAL ROOM	2	EA	
STUCCO CLASS V FINISH	1	LS	
PAINTING	1	LS	
EXISTING UTILITIES TO BE RELOCATED UNDER BRIDGE (ALLOWANCE)	1	LS	

Item Description	Quantity	U/M	Amount
<b>MOUNTABLE GRAPHICS (NAUTICAL THEMED MURAL)</b>			
SCAFFOLDING FOR MLCI AND OTHER TRADES	1	LS	\$511,500.00
METAL FURRING STRIP, TRIM/BACKING WORK FOR SIGNAGE	1	LS	
NAUTICAL GRAPHICS/SIGNAGE	6000	SF	
<b>LANDSCAPING</b>			\$40,000.00
JATROPHA 6'	12	EA	
SOLITARE PALM DB 10'CT	4	EA	
SABAL PALM 10-14'CT	10	EA	
COCOPLUM	150	EA	
GREEN ISLAND FICUS	303	EA	
SELOME	113	EA	
PLUMBAGO	176	EA	
TRINNETE	112	EA	
BAHIA SOD	1276	SF	
3" MULCH	1	LS	
12" TOPSOIL	197	CY	
TREE STAKING INCL. PAINT	14	EA	
PRE-EMERGENT/POST EMERGENT/SOIL AMENDMENTS			
1 YEAR LANDSCAPE MAINTENANCE			
			<b>INCLUDED IN PRICING</b>
			<b>NOT INCLUDED IN PRICING</b>
<b>IRRIGATION</b>			\$25,900.00
IRRIGATION SYSTEM COMPLETE (INCLUDING BUT NOT LIMITED TO)	1	LS	
BACKFLOW PREVENTER WITH ENCLOSURE			
POINTS OF CONNECTIONS			
QUICK COUPLERS			
CONTROLLER WITH PEDESTAL AND ENCLOSURE			
SCHEDULE 40 PVC SLEEVES			
SCHEDULE 40 PVC MAINLINE & LATERALS			
RAINBIRD VALVES, RAINBIRD VALVE BOXES, WIRE			
RAINBIRD SPRAY HEADS			
BUBBLERS			
<b>FUTURE FLOATING PEDESTRIAN WALK (N.I.C.)</b>			
ATLANTIC BLVD. BRIDGE IMPROVEMENTS; GUARANTEED MAXIMUM PRICE (GMP)			\$4,653,860.00
<b>OWNER'S CONTINGENCY</b>			\$345,000.00
ATLANTIC BLVD. BRIDGE IMPROVEMENTS; TOTAL BUDGET			\$4,998,860.00



Burkhardt Construction, Inc.

Printed on Mon Jun 12, 2017 at 10:33 am EDT  
 Job #: 1403 Atlantic Blvd. Bridge Improvements  
 Atlantic Boulevard Bridge over the Intracoastal Waterway

**Current Drawings**

Drawing No.	Drawing Title	Revision No.	Drawing Date	Received Date	Set
<b>ALL</b>					
A0.0	CONSTRUCTION DRAWINGS	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
A0.1	DRAWING INDEX	3	09/14/2016	06/05/2017	Permit Set (09/16/16)
<b>Architectural</b>					
A1.0	SITE PLAN	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
A1.1	ENLARGED WEST SITE PLAN	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
A1.2	ENLARGED EAST SITE PLAN	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
A1.3	PROMENADE PLAN	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
A2.0	ELECTRICAL ROOM PLAN	2	09/14/2016	06/05/2017	Permit Set (09/16/16)
A2.1	TENDER HOUSE PLAN	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
A2.2	TENDER HOUSE ROOF PLAN	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
A2.3	CUPOLA FRAMING DETAILS	2	09/14/2016	06/05/2017	Permit Set (09/16/16)
A3.0	OVERALL ELEVATIONS	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
A3.1	NORTHEAST TENSILE STRUCTURE ELEVATIONS	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
A3.2	SOUTHEAST TENSILE STRUCTURE ELEVATIONS	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
A3.3	SOUTHWEST TENSILE STRUCTURE ELEVATIONS	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
A3.4	NORTHWEST TENSILE STRUCTURE ELEVATIONS	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
A3.5	TENDER HOUSE ELEVATIONS	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
A3.6	TENDER HOUSE ELEVATIONS	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
A3.7	TENDER HOUSE ELEVATION	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
A3.8	EAST BASCULE MURAL ELEVATIONS	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
A3.9	WEST BASCULE MURAL ELEVATIONS	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
A6.0	PROMENADE REFLECTED CEILING PLAN	3	09/14/2016	06/05/2017	Permit Set (09/16/16)
A6.1	BASCULE REFLECTED CEILING PLAN	2	09/14/2016	06/05/2017	Permit Set (09/16/16)
A7.0	TENDER HOUSE SECTION	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
A7.1	TENDER HOUSE SECTIONS	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
A7.2	TENDER HOUSE / CUPOLA SECTIONS	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
A7.3	TENDER HOUSE / CUPOLA SECTIONS	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
A7.4	BRIDGE SECTIONS	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
A7.5	PROMENADE SECTION	3	09/14/2016	06/05/2017	Permit Set (09/16/16)
A7.6	WALL SECTIONS	3	09/14/2016	06/05/2017	Permit Set (09/16/16)
A8.0	ENLARGED DETAILS	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
A8.1	MURAL DETAILS	2	09/14/2016	06/05/2017	Permit Set (09/16/16)
A9.1	TENDER HOUSE RENDERING	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
A10.1	STREET VIEW WITH TENSILE STRUCTURES	3	09/14/2016	06/05/2017	Permit Set (09/16/16)
A10.2	STREET VIEW WITH TENSILE STRUCTURES	3	09/14/2016	06/05/2017	Permit Set (09/16/16)
A10.3	STREET VIEW WITH TENSILE STRUCTURES	3	09/14/2016	06/05/2017	Permit Set (09/16/16)
D1.0	TENDERHOUSE DEMOLITION PLAN/SECTION	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
<b>Landscape</b>					



Burkhardt Construction, Inc.

Printed on Mon Jun 12, 2017 at 10:33 am EDT  
 Job #: 1403 Atlantic Blvd. Bridge Improvements  
 Atlantic Boulevard Bridge over the Intracoastal Waterway

Drawing No.	Drawing Title	Revision No.	Drawing Date	Received Date	Set
L1.1	LANDSCAPE PLAN	4	10/31/2016	06/05/2017	Permit Set (09/16/16)
L1.2	LANDSCAPE DETAILS	4	10/31/2016	06/05/2017	Permit Set (09/16/16)
L1.3	LANDSCAPE NOTES	4	10/31/2016	06/05/2017	Permit Set (09/16/16)
<b>Structural</b>					
S1.0	PROMENADE PLAN VIEW	3	09/14/2016	06/05/2017	Permit Set (09/16/16)
S1.1	PROMENADE TYPICAL SECTION	3	09/14/2016	06/05/2017	Permit Set (09/16/16)
S1.2	PROMENADE STRUCTURAL DETAILS	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
S1.3	PROMENADE STRUCTURAL DETAILS	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
S2.0	BRIDGE RAILING REPLACEMENT GENERAL NOTES (1 OF 2)	3	09/14/2016	06/05/2017	Permit Set (09/16/16)
S2.1	BRIDGE RAILING REPLACEMENT GENERAL NOTES (2 OF 2)	3	09/14/2016	06/05/2017	Permit Set (09/16/16)
S2.2	BRIDGE RAILING REPLACEMENT GENERAL PLAN	3	09/14/2016	06/05/2017	Permit Set (09/16/16)
S2.3	BRIDGE RAILING REPLACEMENT BRIDGE RAILING PLAN	3	09/14/2016	06/05/2017	Permit Set (09/16/16)
S2.4	BRIDGE RAILING REPLACEMENT TYPICAL SECTION (1 OF 2)	3	09/14/2016	06/05/2017	Permit Set (09/16/16)
S2.5	BRIDGE RAILING REPLACEMENT TYPICAL SECTION (2 OF 2)	3	09/14/2016	06/05/2017	Permit Set (09/16/16)
S2.6	BRIDGE RAILING REPLACEMENT WYOMING RAIL (TL-4) DETAILS (1 OF 4)	3	09/14/2016	06/05/2017	Permit Set (09/16/16)
S2.7	BRIDGE RAILING REPLACEMENT WYOMING RAIL (TL-4) DETAILS (2 OF 4)	3	09/14/2016	06/05/2017	Permit Set (09/16/16)
S2.8	BRIDGE RAILING REPLACEMENT WYOMING RAIL (TL-4) DETAILS (3 OF 4)	1	09/14/2016	06/05/2017	Permit Set (09/16/16)
S2.9	BRIDGE RAILING REPLACEMENT WYOMING RAIL (TL-4) DETAILS (4 OF 4)	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
S2.10	TRAFFIC RAILING REPLACEMENT BARRIER TRANSITION "A" (1 OF 2)	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
S2.11	TRAFFIC RAILING REPLACEMENT BARRIER TRANSITION "A" (2 OF 2)	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
S2.12	TRAFFIC RAILING REPLACEMENT BARRIER TRANSITION "B" (1 OF 2)	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
S2.13	TRAFFIC RAILING REPLACEMENT BARRIER TRANSITION "B" (2 OF 2)	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
S2.14	TRAFFIC RAILING REPLACEMENT BARRIER TRANSITION "C" (1 OF 2)	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
S2.15	TRAFFIC REPLACEMENT BARRIER TRANSITION "C" (2 OF 2)	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
S2.16	BRIDGE RAILING REPLACEMENT REINFORCING BAR BENDING DIAGRAM	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
S2.17	BRIDGE RAILING REPLACEMENT REMOVAL OF EXISTING STRUCTURE	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
S2.18	TRAFFIC RAILING TRANSITION PLAN	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
S2.19	TRAFFIC RAILING TRANSITION PLAN	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
<b>Electrical</b>					
E-1.1	PROMENADE EAST WALKWAY LIGHTING PLAN	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
E-1.2	PROMENADE WEST WALKWAY LIGHTING PLAN	4	09/14/2016	06/05/2017	Permit Set (09/16/16)
E-1.3	BASCULE PIER LIGHTING PLAN	2	09/14/2016	06/05/2017	Permit Set (09/16/16)
E-1.4	PROMENADE EAST LIGHTING PLAN	2	09/14/2016	06/05/2017	Permit Set (09/16/16)
E-1.5	SITE LIGHTING WEST PANEL SCHEDULE & ELECTRICAL RISER	1	09/14/2016	06/05/2017	Permit Set (09/16/16)
E-1.6	SITE LIGHTING EAST PANEL SCHEDULE & ELECTRICAL RISER	1	09/14/2016	06/05/2017	Permit Set (09/16/16)
L-0	LIGHTING PHOTOMETRICS	1	09/14/2016	06/05/2017	Permit Set (09/16/16)
L-1	POLE DETAILS	1	09/14/2016	06/05/2017	Permit Set (09/16/16)
L-2	POLE DETAILS	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
<b>EXISTING CONDITIONS</b>					
EX-1	EXISTING BRIDGE PLAN-EAST	0	11/16/2015	11/17/2015	95% Drawings (11/16/15)
EX-2	EXISTING BRIDGE PLAN - WEST	0	11/16/2015	11/17/2015	95% Drawings (11/16/15)
<b>IRRIGATION</b>					
L2.1	IRRIGATION PLAN	0	10/31/2016	06/05/2017	Permit Set (09/16/16)





Burkhardt Construction, Inc.

Printed on Mon Jun 12, 2017 at 10:33 am EDT

Job #: 1403 Atlantic Blvd. Bridge Improvements  
Atlantic Boulevard Bridge over the Intracoastal Waterway

Drawing No.	Drawing Title	Revision No.	Drawing Date	Received Date	Set
I.2.2	IRRIGATION DETAILS	0	10/31/2016	06/05/2017	Permit Set (09/16/16)
<b>MOT</b>					
T1.0	TRAFFIC CONTROL PLAN GENERAL NOTES	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
T1.1	TRAFFIC CONTROL PLAN TYPICAL SECTION	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
T1.2	TRAFFIC CONTROL PLAN TYPICAL SECTION	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
T1.3	TRAFFIC CONTROL PLAN PHASE I	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
T1.4	TRAFFIC CONTROL PLAN PHASE I	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
T1.5	TRAFFIC CONTROL PLAN PHASE II	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
T1.6	TRAFFIC CONTROL PLAN PHASE II	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
<b>Tensile Structure</b>					
A-100	PLAN & ELEVATION	2	09/14/2016	06/05/2017	Permit Set (09/16/16)
A-100.1	PLAN & ELEVATION AT WEST NORTH	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
A-100.2	PLAN & ELEVATION AT WEST SOUTH	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
A-100.3	PLAN & ELEVATION AT EAST NORTH	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
A-100.4	PLAN & ELEVATION AT EAST SOUTH	0	09/14/2016	06/05/2017	Permit Set (09/16/16)
A-101	VIEW & DETAILS	2	09/14/2016	06/05/2017	Permit Set (09/16/16)
A-101.1	STAY CABLE LAYOUT DETAIL	2	09/14/2016	06/05/2017	Permit Set (09/16/16)
A-102	FOOTING DETAIL	2	09/14/2016	06/05/2017	Permit Set (09/16/16)
A-103	FABRIC DETAIL	2	09/14/2016	06/05/2017	Permit Set (09/16/16)
TS	GENERAL NOTES & DRAWING TITLE	1	09/14/2016	06/05/2017	Permit Set (09/16/16)
TS.1	SITE PLAN	1	09/14/2016	06/05/2017	Permit Set (09/16/16)
TS.2	SITE PLAN "A"	2	09/14/2016	06/05/2017	Permit Set (09/16/16)
TS.3	SITE PLAN "B"	2	09/14/2016	06/05/2017	Permit Set (09/16/16)
<b>Utility</b>					
U1.0	UTILITY GENERAL NOTES	3	09/14/2016	06/05/2017	Permit Set (09/16/16)
U1.1	UTILITY LOCATION PLAN- WEST	3	09/14/2016	06/05/2017	Permit Set (09/16/16)
U1.2	UTILITY LOCATION PLAN- EAST	0	09/14/2016	06/05/2017	Permit Set (09/16/16)