


1. THE CONTRACTOR SHALL TAKE NECESSARY PRECAUTIONS TO PREVENT CONTAMINATION OF THE TRENCH BY SAND, SILT, OR OTHER MATERIAL.
2. THE CONTRACTOR SHALL INSTALL
 - A. PERFORATED RCP IN ACCORDANCE WITH F.D.O.T. REQUIREMENTS.
 - B. CORRUGATED ALUMINUM IN ACCORDANCE WITH F.D.O.T. REQUIREMENTS.
3. NO PIPE PERFORATIONS FOR THE FIRST 5 FEET FROM THE INLET OR MANHOLE.
4. PIPE PERFORATIONS SHALL BE PER FDOT REQUIREMENTS
5. SEE DETAILS OF MANHOLE AND/OR INLET FOR CONSTRUCTION DETAILS OF SAME.
6. PLASTIC FILTER FABRIC SHALL CONFORM TO D.O.T. SECTION 985 OR APPROVED EQUAL.
7. PRIOR TO BACKFILLING ANY DRAINAGE STRUCTURES, THE CITY ENGINEERING DEPARTMENT SHALL BE GIVEN 24 HOURS NOTICE IN ORDER TO SCHEDULE AN INSPECTION OF THE FACILITY.

N.T.S.



DATE 05/28/2005
DRAWN BY DJP
F.B./ PG. ---
SCALE N/

MATTHEW V. KAHN
PROFESSIONAL ENGINEER
LICENSE NO. 8222
STATE OF FLORIDA
- FOR THE FIRM -
DATE

JOB # 11146
SHT. NO.
PD-7
OF 16 SHEETS

DRC

PZ25-12000016

10/01/2025