



CITY OF POMPANO BEACH

P.O. DRAWER 1300
ATTN: ACCOUNTS PAYABLE
POMPANO BEACH, FL 33061

AN EQUAL OPPORTUNITY EMPLOYER

**PURCHASE
ORDER NO.**

351231

Type: S

DATE: 06/18/2025

51301
(954)532-1918

TO: DBF CONSTRUCTION LLC
240 SW 12 AVE STE 2
POMPANO BEACH, FL 33069

SHIP TO: SEWER PUMPING
SEWER PUMPING
(954) 786-4082
1201 NE 3RD AVENUE
POMPANO BEACH, FL 33060

Our P.O. # MUST Appear on ALL Invoices, Packages and Correspondence

DELIVER BY	REQUISITION #	REQUISITION DATE	TERMS	CONFIRMED BY
09/30/2025	3025001844	06/05/2025	NET	LEF / B. CLAYTON
FOB	CONTRACT#	ACCOUNT NUMBER	PROJECT#	AUTHORIZED BY
DESTINATION		42076235356512	19345	MICHAEL LEE

Item #	Quantity / Unit	Description/Remarks	Unit Cost	Extended Cost
1	308,544.29 DL	968 065 PUBLIC WORKS/CONSTR SVCS PIPE LINE CONSTRUCTION EMERGENCY REPAIR SERVICES FOR FORCE MAIN REPAIR	1.0000	308,544.29

Force Main Break Location: 1100 S. Federal HY.

MOB/DEMOB/Dewatering/Pumping. Excavation of 16"
Force Main,
All necessary materials and pipe for up to 20 LF
of pipe, Hauling away all contaminated fill,
importing clean dry fill with LBR material,
Compaction in 6"-1' lifts Densities, 16" Lime rock
compacted in 6" Lifts.
(2) 1.5 inch lifts of asphalt Per FDOT inspection
due to milling and overlay project.
Removal of 6" concrete approach and F-Curb and
replace with 4,000 PSI fiber concrete,
F-Curb will require 6" Lime rock compacted base.
Complete sod and irrigation
Price = \$308,544.29

QUOTE DATE: 06/02/2025

PLEASE NOTE THAT QUANTITY AND UNIT COST HAVE BEEN
REVERSED. THIS WILL ALLOW US TO PROCESS PARTIAL
PAYMENTS TO YOUR COMPANY, WHEN APPLICABLE. THE
TOTAL ORDER IS REFLECTED IN THE PURCHASE ORDER
TOTAL.

" SERVICE PURCHASE ORDER"