

Ocy 22

ORDINANCE NO. 2017- 59

**CITY OF POMPANO BEACH
Broward County, Florida**

AN ORDINANCE OF THE CITY OF POMPANO BEACH, FLORIDA, REZONING PROPERTY LOCATED AT THE SOUTHWEST CORNER OF 15TH STREET AND NW 6TH AVENUE FROM RM-12 (MULTIPLE-FAMILY RESIDENCE) TO RPUD (RESIDENTIAL PLANNED UNIT DEVELOPMENT); PROVIDING FOR SEVERABILITY; PROVIDING AN EFFECTIVE DATE.

WHEREAS, pursuant to law, ten (10) days' notice has been given by publication in a paper of general circulation in the City, notifying the public of this proposed ordinance and of a public hearing in the City Commission Chambers of the City of Pompano Beach, Florida; and

WHEREAS, in accordance with Section 155.2305.C, of the Pompano Beach Code of Ordinances, notice in accordance with said section has been mailed notifying residents within 500 feet of the subject property of two public hearings on this proposed Ordinance; and

BE IT ENACTED BY THE CITY OF POMPANO BEACH, FLORIDA:

SECTION 1. - FINDINGS: The City Commission finds as follows: that the rezoning of the property described herein is consistent with the Comprehensive Plan; that the rezoning complies with Section 135.3602., General Standards for All Planned Development Districts, as well as all other requirements of the Zoning Code; that the rezoning does not have a potentially injurious effect on land adjacent to the rezoned parcel; and that rezoning is reasonably related to the public health, safety and welfare.

SECTION 2. - REZONING AND APPROVAL OF PLANNED DEVELOPMENT PLAN:
The property more particularly described in Exhibit "A," attached hereto and made a part hereof ("Property"), which is hereby rezoned from a present zoning classification of a RM-12 (Multiple-Family Residence) zoning classification to RPUD (Residential Planned Unit Development) as said zoning classification is defined in Section 155.3603., Residential Planned Unit Development, of the Code of Ordinances of the City of Pompano Beach, Florida.

Pursuant to the requirements of Section 155.3602 and Section 155.3603 of the Code of Ordinances of the City of Pompano Beach, Florida, the Planned Development Plan ("Plan") submitted for the Property, attached hereto and made a part hereof as Exhibit "B," is hereby adopted. All development of the Property shall proceed in accordance with the Plan, as approved, and Section 155.3603 of the Code of Ordinances of the City of Pompano Beach.

SECTION 3. – EFFECTIVE PERIOD OF APPROVAL: Approval of this rezoning shall automatically expire if an application for a Site Plan (Major or Minor) for any part of the development shown on the approved Plan is not submitted within two years after approval of the RPUD, or an extension of this time period authorized in accordance with Section 155.2308.B.2, Extension of Expiration Time Period.

SECTION 4. - SEVERABILITY: If any provision of this Ordinance or the application thereof to any person or circumstance is held invalid, such invalidity shall not affect other provisions or applications of this Ordinance that can be given effect without the invalid provision or application, and to this end the provisions of this Ordinance are declared to be severable.

SECTION 5. This Ordinance shall become effective upon passage.

PASSED FIRST READING this 11th day of July, 2017.

PASSED SECOND READING this 25th day of July, 2017.



LAMAR FISHER, MAYOR

ATTEST:



ASCELETA HAMMOND, CITY CLERK

/jrm
5/30/17
l:ord/2017-231

EXHIBIT A 1 OF 2

Legal Description

PARCEL "A", **ABYSSINIAN BAPTIST CHURCH OF CHRIST**, ACCORDING TO THE PLAT THEREOF, AS RECORDED IN PLAT BOOK 167, AT PAGE 22 OF THE PUBLIC RECORDS OF BROWARD COUNTY FLORIDA.

TOGETHER WITH;


ALL THAT PART OF THE NW 1/4 OF THE NE 1/4 OF THE NW 1/4 LYING WEST OF AND ADJACENT TO NW 6TH AVENUE, LESS THE F.E.C. RAILROAD RIGHT OF WAY OF THE SOUTH 150 FEET AND NORTH 35 FEET WHICH HAS BEEN DEDICATED FOR ROAD RIGHT-OF-WAY OF NW 15TH STREET, ALL IN SECTION 35, TOWNSHIP 48 SOUTH, RANGE 42 EAST, BROWARD COUNTY, FLORIDA;

AND

THE EAST 100 FEET OF THE E 1/2 OF THE NE 1/4 OF THE NW 1/4 OF THE NW 1/4, EXCEPT THE SOUTH 150 FEET FOR FLORIDA EAST COAST RIGHT-OF-WAY AND EXCEPT THE NORTH 35 FEET THEREOF, DEDICATED FOR STREET RIGHT-OF-WAY, IN SECTION 35, TOWNSHIP 48 SOUTH, RANGE 42 EAST, BROWARD COUNTY, FLORIDA.

SAID LANDS SITUATE IN THE CITY OF POMPANO BEACH, BROWARD COUNTY, FLORIDA, AND CONTAIN 9.035 ACRES, MORE OR LESS.

Folio # 484235750010 & 4842 35 75 0010 & 4842 35 00 0280



LEGAL DESCRIPTION

PARCEL "A", ABYSSINIAN BAPTIST CHURCH OF CHRIST, ACCORDING TO THE PLAT THEREOF, AS RECORDED IN PLAT BOOK 167, AT PAGE 22 OF THE PUBLIC RECORDS OF BROWARD COUNTY, FLORIDA.

TOGETHER WITH:

ALL THAT PART OF THE NW 1/4 OF THE NE 1/4 OF THE NW 1/4 LYING WEST OF AND ADJACENT TO NW 6TH AVENUE, LESS THE F.E.C. RAILROAD RIGHT-OF-WAY OF THE SOUTH 150 FEET AND NORTH 35 FEET WHICH HAS BEEN DEDICATED FOR ROAD RIGHT-OF-WAY OF NW 15TH STREET, ALL IN SECTION 35, TOWNSHIP 48 SOUTH, RANGE 42 EAST, BROWARD COUNTY, FLORIDA;

AND

THE EAST 100 FEET OF THE E 1/2 OF THE NE 1/4 OF THE NW 1/4, EXCEPT THE SOUTH 150 FEET FOR FLORIDA EAST COAST RIGHT-OF-WAY AND EXCEPT THE NORTH 35 FEET THEREOF, DEDICATED FOR STREET RIGHT-OF-WAY, IN SECTION 35, TOWNSHIP 48 SOUTH, RANGE 42 EAST, BROWARD COUNTY, FLORIDA.

SAD LANDS SITUATE IN THE CITY OF POMPANO BEACH, BROWARD COUNTY, FLORIDA.

NOTES:

- THIS DRAWING IS NOT VALID WITHOUT THE SIGNATURE AND THE ORIGINAL RAISED SEAL OF A FLORIDA LICENSED SURVEYOR AND MAPPER.
- THERE HAVE BEEN NO UNDERGROUND IMPROVEMENTS LOCATED IN CONNECTION WITH THIS SURVEY, EXCEPT AS SHOWN.
- RECORDING INFORMATION REFERS TO BROWARD COUNTY PUBLIC RECORDS UNLESS OTHERWISE INDICATED.
- THE AREA OF THIS PROPERTY IS 9.035 ACRES, MORE OR LESS.
- ELEVATIONS SHOWN HEREON ARE RELATIVE TO THE NAD 88 AND WERE DETERMINED FROM BROWARD COUNTY ENGINEERING BENCHMARK #2621, ELEVATION 10.00' (CONVERTED FROM THE PUBLISHED ELEVATION OF 11.57' NVD 29).
- FEMA FLOOD ELEVATION INFORMATION:
A. FIRM NO.: 1201100357H
B. EFFECTIVE DATE: AUGUST 18, 2014
C. ZONE: AE & AH
D. BASE FLOOD EL.: 11' & 12'
- BEARINGS SHOWN HEREON ARE BASED ON THE NORTH LINE OF PARCEL "A", ABYSSINIAN CHURCH OF CHRIST, HAVING AN ASSUMED BEARING OF NORTH 88°16'45" EAST.
- TREE TYPES WERE DETERMINED TO THE BEST OF OUR KNOWLEDGE. EXACT SPECIES SHOULD BE DETERMINED BY A LICENSED BOTANIST OR OTHER PROFESSIONAL WITH SUCH CAPACITY.
- TEMPORARY CONSTRUCTION FENCES ARE NOT SHOWN HEREON.

ABBREVIATIONS:

A = ARC LENGTH
A/C = AIR CONDITIONER
ALUM. = ALUMINUM
B.C.R. = BROWARD COUNTY RECORDS
BOT = BOTTOM
BRN = BROKEN
CB = CATCH BASIN
C.B.S. = CONCRETE BLOCK & STUCCO
CLF = CHAIN LINK FENCE
CMP = CORRUGATED METAL PIPE
CONC. = CONCRETE
D = DELTA (CENTRAL ANGLE)
D.E. = DRAINAGE EASEMENT
ELEV. = ELEVATION
F.F. = FINISHED FLOOR
FIP = FOUND IRON PIPE
FR/C = FOUND IRON ROD W/CAP
FR = FOUND IRON ROD
FND. = FOUND
INV = INVERT
L.B. = LANDSCAPE BUFFER
MON. = MONUMENT
N/D = NAIL AND DISC
P.B. = PLAT BOOK
PC = PAGE
R = RADIUS
R/W = RIGHT-OF-WAY
SRW/C = SET 1/2" IRON ROD W/CAP LB7924
SMH = SANITARY SEWER MANHOLE
SN/D = SET NAIL & DISC LB7924
SQ. = SQUARE
STT. = STORY
TCB = TRAFFIC CONTROL BOX
TYP. = TYPICAL
U.E. = UTILITY EASEMENT
WV = WATER VALVE

LEGEND:

BACKFLOW PREVENTER
BOLLARD
CABLE BOX
CATCH BASIN
CENTERLINE
CLEANOUT
ELEVATION
FIRE HYDRANT
MANHOLE, DRAINAGE
MANHOLE, SANITARY
NON-VEHICULAR ACCESS LINE
POLE, LIGHT
POLE, WOOD
SON
TREE
VALVE, WATER
WATER METER
WRES, OVERHEAD
TREE NUMBER

SURVEYOR'S CERTIFICATION:

I HEREBY CERTIFY THAT THE SURVEY SHOWN HEREON MEETS THE STANDARDS OF PRACTICE FOR AND IS ACCORDING TO THE CHARTER, ARTICLE IV, OF THE FLORIDA ADMINISTRATIVE CODE PURSUANT TO CHAPTER 47, F.S., AND IS CONTAINED IN PLAT BOOK 167, AT PAGE 22 OF THE PUBLIC RECORDS OF BROWARD COUNTY, FLORIDA.

DONNA C. HARRIS, SURVEYOR
FLORIDA REGISTRATION NO. LB7924

LAST DATE OF FIELD SURVEY: 03/01/17

TREE No.	TREE - COMMON NAME	DIAMETER at BREAST HEIGHT (in inches)	TREE HEIGHT (in feet)	CANOPY DIAMETER (in feet)
20073	COCONUT PALM	8	15	35
20074	COCONUT PALM	8	10	12
20076	COCONUT PALM	8	20	15
20077	COCONUT PALM	8	20	15
20079	COCONUT PALM	8	15	15
20080	COCONUT PALM	10	20	20
20082	COCONUT PALM	8	15	15
20083	COCONUT PALM	8	15	15
20084	COCONUT PALM	8	20	18
20087	COCONUT PALM	6	8	15
20088	COCONUT PALM	8	15	15
20089	COCONUT PALM	8	10	15
30000	CHRISTMAS PALM	2.5	8	10
30001	CHRISTMAS PALM	2.5	8	10
30002	CHRISTMAS PALM	2.5	8	10
30003	CHRISTMAS PALM	2.5	8	10
30004	CHRISTMAS PALM	2.5	8	10
30005	CHRISTMAS PALM	2.5	8	10
30006	CHRISTMAS PALM	2.5	8	10
30007	CHRISTMAS PALM	2.5	8	10
30008	CHRISTMAS PALM	2.5	8	10
30009	CHRISTMAS PALM	2.5	8	10

TREE No.	TREE - COMMON NAME	DIAMETER at BREAST HEIGHT (in inches)	TREE HEIGHT (in feet)	CANOPY DIAMETER (in feet)
30010	CHRISTMAS PALM	8	30	12
30011	CHRISTMAS PALM	8	30	12
30012	CHRISTMAS PALM	8	30	12
30013	CHRISTMAS PALM	8	30	12
30014	CHRISTMAS PALM	8	30	12
30015	CHRISTMAS PALM	8	30	12
30016	LIVE OAK	4	12	8
30017	UNKNOWN	7	15	15
30018	CHRISTMAS PALM	18	6	12
30019	CHRISTMAS PALM	6	15	12
30020	UNKNOWN PALM	12	8	15
30021	CABBAGE PALM	15	6	12
30022	CABBAGE PALM	15	6	12
30023	CABBAGE PALM	14	16	12
30024	CABBAGE PALM	15	12	12
30025	CABBAGE PALM	15	10	12
30026	CABBAGE PALM	15	30	15
30027	CABBAGE PALM	15	20	15
30028	CABBAGE PALM	15	20	15
30029	CABBAGE PALM	18	20	15
30030	CABBAGE PALM	18	20	15
30031	CABBAGE PALM	15	6	12

TREE No.	TREE - COMMON NAME	DIAMETER at BREAST HEIGHT (in inches)	TREE HEIGHT (in feet)	CANOPY DIAMETER (in feet)
30032	CABBAGE PALM	15	12	12
30033	CABBAGE PALM	15	12	12
30034	CABBAGE PALM	18	20	15
30035	CABBAGE PALM	15	10	12
30036	FICUS	15	15	30
30037	CABBAGE PALM	18	8	15
30038	CABBAGE PALM	18	20	15
30039	CABBAGE PALM	18	8	12
30040	CABBAGE PALM	18	6	12
30041	CABBAGE PALM	15	10	12
30042	CABBAGE PALM	10	12	12
30043	CABBAGE PALM	10	12	12
30044	CABBAGE PALM	10	12	12
30045	CABBAGE PALM	10	12	12
30046	CABBAGE PALM	10	12	12
30047	BANYAN	12	15	30
30048	BANYAN	12	15	30
30049	CABBAGE PALM	18	18	12
30050	CABBAGE PALM	18	12	12
30051	BANYAN	10	15	10
30052	UNKNOWN	6	10	12
30053	LIVE OAK	6	15	20

TREE No.	TREE - COMMON NAME	DIAMETER at BREAST HEIGHT (in inches)	TREE HEIGHT (in feet)	CANOPY DIAMETER (in feet)
30054	CABBAGE PALM	18	6	12
30055	CABBAGE PALM	18	6	12
30056	LIVE OAK	4	10	10
30057	LIVE OAK	6	10	12
30058	CABBAGE PALM	15	12	12
30059	CABBAGE PALM	15	12	12
30060	BANYAN	10	15	20
30061	LIVE OAK	4	10	8

NO.	DATE	BY	CHKD	REVISIONS
3	3/8/17	JOV	DCW	UPDATE SURVEY
2	9/1/16	DCW	DCW	ADD EASEMENTS PER TITLE OPINION
1	12/31/14	LWK	DCL	ADD IMPROVEMENTS, TOPOGRAPHY, AND TREES

SCALE: 1"=40'
DATE: 07/01/14
DRAWN BY: DCL
FIELD BOOK: 013/44
CHECKED BY: DCW
SURVEY TYPE: BOUNDARY



HSQ GROUP, INC.
Engineers • Planners • Surveyors
1489 West Palmetto Park Road, Suite 340
Boca Raton, Florida 33486 • 561.392.0221
CA26258 • LB7924

MAP OF BOUNDARY, TOPOGRAPHIC, AND TREE SURVEY
"RICK CASE HABITAT COMMUNITY"
CITY OF POMPANO BEACH, BROWARD COUNTY, FLORIDA

PROJECT NUMBER
1406-34
SHEET NUMBER
1 OF 1

HABITAT FOR HUMANITY

NW 6TH AVENUE NW 15TH STREET PARCEL

RESIDENTIAL PLANNED UNIT DEVELOPMENT

for 77 single family homes on 9.03 net acres

CITY OF POMPANO BEACH, FL

Submitted June 15, 2017

Prepared for:

Habitat for Humanity



LETTER OF TRANSMITTAL

CITY OF POMPANO BEACH

Mr. Robin Bird
Director of Development Services
100 West Atlantic Boulevard
Pompano Beach, Florida 33060



DEVELOPER INFORMATION AND SITE LOCATION

DEVELOPER

Habitat for Humanity of Broward
Nancy Robin
Executive Director
3564 North Ocean Boulevard
Fort Lauderdale, FL 33308
954.396.3030 Ext. 201 Office

LEGAL / AGENT

Michelle J. Gomez, Esq.
Saunders, Curtis, Ginestra & Gore, PA
954-969-9919 x1166 office
954-263-1918 cell
8201 Peters Road, Suite 2001
Fort Lauderdale, FL 33324

ENGINEER/PLANNER/SURVEYOR

HSQ Group, Inc.
Jay M. Huebner, P.E.
1489 W. Palmetto Park Road, Suite 340
Boca Raton, Florida 33486
(561) 392-0221

Dennis Mele
Greenspoon Marder
200 East Broward Blvd.
Suite 1800
Fort Lauderdale, Fl 33301
(954) 761-2923

ARCHITECT

The Benedict Group
Tom Benedict, Architect
1525 N.W. 3rd Street, Suite #1
Deerfield Beach, Fl. 33442
(954) 570-9500 Ext. 12

LANDSCAPE ARCHITECT

Scott Davidson, RLA
10610 NW 43rd Street
Coral Springs, Fl 33065
(954) 649-6688

OWNER REPRESENTATIVE

Sharpe Project Developments, Inc.
1212 S. Andrews Ave. #203
Fort Lauderdale, Fl 33316
(954) 832-9095

Prepared by:



TABLE OF CONTENTS

SECTION	ITEM
1.	RPUD PLAN
2.	STATEMENT OF PLANNING OBJECTIVES FOR THE DISTRICT
3.	GENERAL SITE INFORMATION
4.	EXISTING AND PROPOSED USES
5.	PROJECT DENSITY AND POPULATION
6.	PROPOSED COMMERCIAL USAGE
7.	PLAN FOR CIRCULATION, STREETS AND PARKING
8.	PLAN FOR OPEN SPACE AND RECREATION FACILITY
9.	PROVISIONS FOR WATER, SEWER AND UTILITIES SERVICES
10.	CONSISTENCY WITH CITY PLANS
11.	COMPATIBILITY WITH SURROUNDING AREAS
12.	DEVELOPMENT PHASING PLAN
13.	DEVELOPMENT CONVERSION SCHEDULE
14.	ON-SITE PUBLIC FACILITIES
15.	DEDICATION OF LAND TO CITY, COUNTY AND STATE
16.	USES
17.	DENSITIES/ INTENSITIES
18.	DIMENSIONAL STANDARDS
19.	DEVELOPMENT STANDARDS
20.	TYPICAL UNIT ALLOWANCES
21.	SUSTAINABILITY
22.	TREE PRESERVATION
23.	MODIFICATIONS - PERIMETER FENCE
24.	Exhibit A Location map
25.	Exhibit B Legal Description and Survey
26.	Exhibit C Intensity and Dimension Standards
27.	Exhibit D Regulating PD Plan
28.	Exhibit E Typical Unit Landscape Plan
29.	Exhibit F Typical Residential Plans
30.	Exhibit G Ped. Circulation, Rec., Open Space
31.	Exhibit H Building Use Plan
32.	Exhibit I Schematic Utilities Layout
33.	Exhibit J Utility Plan
34.	Exhibit K Phasing plan.

1. RPUD PLAN

A. EXISTING USE:

The existing site is vacant improved land with little vegetation located on the corner of 6 Avenue and NW 15 Street. It is rectangular in shape approximately 480' x 825' or 9.03 Acres.



B. Habitat for Humanity

Vision

A world in which everyone has a decent place to live. Revitalize and strengthen the community by building affordable homes throughout Broward County. Teach the youth of future homeowner families the skills and attitudes needed to make better life choices and break the intergenerational cycle of poverty. Increase awareness and educate the community regarding issues related to the affordable housing crisis and what they can do to help. Empower partner families through education, resources and support to successfully achieve their personal, academic and professional goals.

Mission Statement

Seeking to put God's love into action, Habitat for Humanity brings people together to build homes, communities and hope.

Mission Principle

1. Demonstrate the Love of Jesus Christ
2. Focus on Shelter
3. Advocate for Affordable Housing
4. Promote Dignity and Hope
5. Support Sustainable and Transformational Development

Non-Proselytizing Policy

Habitat for Humanity International and its affiliated organizations will not proselytize. Nor will HFH work with entities or individuals who insist on proselytizing as part of their work with HFH. This means that HFH will not offer assistance on the expressed or implied condition that people must adhere to or convert to a particular faith or listen and respond to messaging designed to induce conversion to a particular faith.

C. Legal description of the area proposed project.

PARCEL "A" ABYSSINIAN BAPTIST CHURCH OF CHRIST, ACCORDING TO THE PLAT THEREOF, AS RECORDED IN PLAT BOOK 167, AT PAGE 22 OF THE PUBLIC RECORDS OF BROWARD COUNTY FLORIDA.

TOGETHER WITH;

ALL THAT PART OF THE NW ¼ OF THE NE ¼ OF THE NW ¼ LYING WEST OF AND ADJACENT TO NW 6TH AVENUE, LESS THE F.E.C. RAILROAD RIGHT OF WAY OF THE SOUTH 150 FEET AND NORTH 35 FEET WHICH HAS BEEN DEDICATED FOR ROAD RIGHT-OF-WAY OF NW 15TH STREET, ALL IN SECTION 35, TOWNSHIP 48 SOUTH, RANGE 42 EAST, BROWARD COUNTY, FLORIDA;

AND

THE EAST 100 FEET OF THE E ½ OF THE NE ¼ OF THE NW ¼ OF THE NW ¼, EXCEPT THE SOUTH 150 FEET FOR FLORIDA EAST COAST RIGHT-OF-WAY AND EXCEPT THE NORTH 35 FEET THEREOF, DEDICATED FOR STREET RIGHT-OF-WAY, IN SECTION 35, TOWNSHIP 48 SOUTH, RANGE 42 EAST, BROWARD COUNTY, FLORIDA.

2. STATEMENT OF PLANNING OBJECTIVES FOR THE DISTRICT

The following city policies are met as follows:

Policy 01.03.01 – Consider the preservation of established single family neighborhoods in all rezoning, land use plan amendments and site plan approvals.

This project rezoning to RPUD allows for single family homes to be constructed. The RPUD is based upon single family only community to be consistent with the surrounding residential uses and meets the wishes of the community per previous town hall meetings.

Policy 01.03-.05 – All Land Use Plan map amendments and rezoning shall provide for the orderly transition of varying residential land use designations.

The proposed RPUD is a rezoning from RM-12 to RPUD to allow for zero lot line single family units and 5' side setbacks in a residential land use category. The surrounding residential uses are single family RS-4 zoning with a lower density residential use. This amendment allows for a residential transition to higher density while still utilizing single family homes to remain compatible with the surrounding residential community.

Policy 01.03-11 – Consider the compatibility of adjacent land uses in all Land Use Plan amendments and rezoning.

The proposed rezoning from RM-12 to RPUD only allows for single family zero lot line and 5' side setbacks development within the RM-12 zoning district. This does not change the overall use or density of the site. The adjacent uses consist of single family homes to the North, Church to the West, High School to the South and Retail to the East. The adjacent uses are compatible with the proposed residential use as the future residents will utilize the church, retails and school facilities as intended without any adverse effects.

Policy 01.07-05 – Through ongoing updates to the land development regulations provide for townhouses and homeowner's associations.

The proposed project is a single-family home on individual lots located on public city streets. The community does not have any common area and the proposed parks will be owned and operated by the City. There is no need for a homeowner's association for this project.

Policy 01-07-22 – The City's land development code shall include provisions to encourage or enable a variety of housing opportunities in varying price ranges, including housing for low and moderate-income families in large scale residential developments.

This project is a Habitat for Humanity community which provides affordable housing for families looking for assistance with home ownership. This will be the largest Habitat for Humanity project in Broward County to date providing for 77 single family units for home ownership.

Planning Objectives:

The objective of the rezoning is to create a residential plan that allows for affordable housing while still providing single family fee simple ownership. Habitat for Humanity consistently provides affordable single-family homes to deserving families. This particular property is best suited for residential homes, but with a 5' side setback design to maximize the number of units and provide a sustainable environment for its residents. The following objectives are used in the creation of this RPUD:

1. Create a higher density residential single-family home community consistent with the underlying land use.
2. Provide a residential community with transportation facilities. The existing property has bus transit stops adjacent to the site.
3. Discourage urban sprawl. This site is in a well-established residential area and will provide much need affordable housing to the local area.
4. Insure utilities are provided to the site. The property will be developed with potable water, sanitary sewer, drainage facilities and waste management pick up.
5. Provide local parks and pedestrian connectivity. The proposed parks are dedicated to the City with pedestrian connectivity to this site and surrounding neighborhoods.
6. Provide close proximity to local schools. This site is directly adjacent to Blanche Ely High School.
7. Plan the overall site to minimize maintenance obligations of the residents. The overall site design allows easy maintenance by the residents and reduced common area expenses.

3. GENERAL SITE INFORMATION

- A. The subject parcel contains approximately 9.03 net acres and 9.96 gross acres and is located at the southwest corner of NW 6th Avenue and NW 15th Street.

B. Proposed site acreage breakdown.

Net site acreage:	9.03 acres.
Pavement/ driveway:	2.42 acres
Sidewalk:	0.34 acres
Building:	1.87 acres
Green area (open Space)	4.35 acres
Right-of-way Dedication:	0.05 acres (5' R/W dedication - NW 6 th Ave)
Park dedication:	0.28 acres

R/W dedication (future platted streets) 2.76 acres.

4. EXISTING AND PROPOSED USES:

The existing site consists of 9.03 acres of vacant land. The proposed use consists of 77 single family residential units with one and two stories not exceeding 35' in height.

5. PROJECT DENSITY AND AREA POPULATION

The current site plan for the development has 77 single family units. The units are 3 and 4 bedrooms with an average of 3.5 persons per unit. The anticipated population is 270 residents.

Pompano Demographics

Source: <https://www.census.gov/quickfacts/table/PST045215/00>

Population estimates, July 1, 2015, (V2015)	107,762
iPopulation estimates base, April 1, 2010, (V2015)	99,844
iPopulation, percent change - April 1, 2010 (estimates base) to July 1, 2015, (V2015)	7.90%
iPopulation, Census, April 1, 2010	99,845
<i>Race and Hispanic Origin</i>	
iWhite alone, percent, April 1, 2010 (a)	62.60%
iBlack or African American alone, percent, April 1, 2010 (a)	28.90%
iAmerican Indian and Alaska Native alone, percent, April 1, 2010 (a)	0.30%
iAsian alone, percent, April 1, 2010 (a)	2.40%
iHispanic or Latino, percent, April 1, 2010 (b)	17.50%
iWhite alone, not Hispanic or Latino, percent, April 1, 2010	50.60%
<i>Housing</i>	
iHousing units, April 1, 2010	
Owner-occupied housing unit rate, 2010-2014	
iMedian value of owner-occupied housing units, 2010-2014	\$154,900
iMedian selected monthly owner costs -with a mortgage, 2010-2014	\$1,498
iMedian selected monthly owner costs -without a mortgage, 2010-2014	\$542
iMedian gross rent, 2010-2014	\$1,075
<i>Education</i>	
iHigh school graduate or higher, percent of persons age 25 years+, 2010-2014	82.80%
iBachelor's degree or higher, percent of persons age 25 years+, 2010-2014	23.10%
<i>Income and Poverty</i>	
iMedian household income (in 2014 dollars), 2010-2014	\$40,534
iPer capita income in past 12 months (in 2014 dollars), 2010-2014	\$24,829
iPersons in poverty, percent	22.8%

6. PROPOSED COMMERCIAL USAGE

The RPUD is residential only and does not include any commercial usage.

7. PLAN FOR CIRCULATION, STREETS AND PARKING

The PD plan for this site is shown on Exhibit D. The current site plan consists of a main entrance from NW 6th Avenue. The site has been designed to meet emergency vehicle access and circulation with a secondary access location to NW 15th Street. The parking requirements are as follows:

Parking requirements:

Required parking for Single Family units is 2 spaces per single family unit.

77 units x 2 = 154 parking spaces

2 parking stalls for community park

Total required: 156 spaces.

Parking provided: 156 spaces

Minimum two parking stalls per unit.

Parking stall associated with driveways in front of units will not be striped. Parking must be in designated parking areas. Garages are not allowed to be enclosed or used for any other purpose than parking if the unit owner has more than one vehicle.

Driveways maximum width of 22'.

No parking in street is allowed except for recreational parks public parking. See exhibit H for more information.

Street design:

The streets will be dedicated to the City of Pompano Beach as public streets. The streets will be designed and constructed to City standards as a 50' wide Right-of-way per city detail 305-1.

The streets will be a minimum of 22' wide with two 11-foot wide travel lanes. The streets will meet the minimum city design standards. The pavement design will be incorporated into the final engineering design of 1-1/2" asphalt, 8" rock base and 12" stabilized sub-grade. All interior streets will be posted 25 miles per hour speed limit.

Driveways shall be designed in accordance with the City of Pompano Beach driveway swale section 305-2. Driveways will be constructed out of concrete.

Pedestrian circulation:

A 5' wide sidewalk is located on both sides of the internal streets and will connect to the sidewalk on NW 6th Avenue and NW 15th Street for mass transit or access to adjacent activities. See exhibit G for more information.

8. PLAN FOR OPEN SPACE AND RECREATION FACILITY

The objective for the open space is to provide usable private yard space to the individual homes. A Habitat for Humanity community works best by limiting the amount of common area facilities that would require a Home owner's association and associated monthly dues. A sustainable Habitat for Humanity single family subdivision requires each home owner to be responsible for their property which in turn limits the burden on the residents for common areas to be maintained at additional costs. The back yards are to remain as open space usage and be comprised of grass and landscape materials. No building expansion, sheds or pools are allowed in backyards. The unit owner can provide for a concrete or brick paver patio to a maximum size of 10'x 10' located at the back door. A covered canopy (canvas or aluminum, no enclosures allowed) is allowed over the patio.

The minimum green area for the site is as follows:

Each unit lot must have a minimum of 25% green space (landscape area).

The overall community shall have a minimum of 30% green area including green swales in the proposed right-of-way and proposed parks.

The RPUD plan dedicates to local parks to the City for a total of 0.28 acres. See Exhibit G for more information.

9. PROVISIONS FOR WATER, SEWER AND UTILITY SERVICES

The required municipal and public services, including fire and police protection, will be available to Habitat for Humanity. The entrance is not gated to allow for quick access to the residents for emergency service vehicles.

Fire Hydrants will be installed in accordance with the City of Pompano Beach Code requirements. Health Care facilities are located within the City for expedient service. Other municipal services such as libraries and regional parks are available within reasonable proximity to the property. See attached exhibit I for details.

A. POTABLE WATER AND SANITARY SEWER ANALYSIS

There are currently adequate public water and wastewater facility available to service the proposed project. A future reuse pipe is proposed for irrigation purposes. The city will connect to the reuse line in the future. The general location of the proposed on-site potable water and wastewater facilities are depicted on exhibit I.

B. DRAINAGE ANALYSIS

As required by regulations of the city of Pompano Beach and Broward County, all storm water will be retained on-site. The general location of proposed on-site storm water management facilities will be depicted on the civil engineering drawings submitted with the site plan.

C. ON-SITE PUBLIC FACILITIES

The proposed roadways will be dedicated to the city for public use. The proposed recreational parks will be dedicated to the city for public use. Solid waste, fire protection and other franchised utilities will be provided to the community. The general public will have access to the roads and parks within the project.

10. CONSISTENCY WITH CITY PLANS

The RPUD zoning designation, is consistent with the existing underlying land use designation M (10-16) and the current zoning of R-12. The RM-12 could allow up to 108 possible units, but the proposed RUPD plan has 77 single family units. The surrounding community is residential or community facility supporting residential needs. The proposed use is consistent with the adjacent uses.

11. COMPATIBILITY WITH SURROUNDING AREAS

The subject site is being developed in a manner that ensures the proposed residential development is context sensitive to the adjoining existing uses. The existing and proposed information is as follows:

Current land use categories of surrounding properties.

Direction	Actual use	Land use category
North	Single family homes	(L) Low 1-5 DU/AC
West	Church	(M) 10-16 DU/AC
South	High School	(M) 10-16 DU/AC / CF
East	Retail/ commercial	(C) Commercial

Current and proposed zoning for the amendment site and adjacent areas.

Direction	Actual use	Zoning district
North	Single family homes	RS-4, RS-3
West	Church	CF
South	High School	CF & B-2 R.R.
East	Retail/ commercial	B-2

Existing use of amendment site and adjacent areas.

Amendment Site	Single family homes (proposed)
North	Single family homes
East	Retail
South	School and rail road tracks (R.R.)
West	Church

The building design of the residential homes is one story around the perimeter and two story in the middle to be consistent with the heights of the residential buildings to the North of the property. The overall design of the site allows for public access to the new public parks and pedestrian connectivity to the surrounding community.

12. DEVELOPMENT PHASING PLAN:

The site infrastructure to include roads, water, sewer, drainage, perimeter fencing, park and walls will be constructed in the first phase. The individual homes are built essentially in sequence until the 77 single family units are constructed. A housing phasing plan will be coordinated with the city prior to construction commencement. See Exhibit K for details.

13. DEVELOPMENT CONVERSION SCHEDULE

There is no conversion schedule associated with the residential uses proposed for the project. The land use and zoning does not allow for commercial uses within the property.

14. ON SITE PUBLIC FACILITIES

The developer will be responsible to design, permit and construct the on-site public facilities to include the roads, potable water, sanitary sewer, park and street lighting. The city park will be graded and include landscape materials as shown on the landscape plans submitted with the site plan. See exhibits G, H, I, and J for more information.

15. DEDICATION OF LAND TO CITY, COUNTY AND STATE

The RPUD development will dedicate the internal roadways to the city for city ownership and future maintenance. Dedication of 5' right-of-way to NW 6th Avenue. Dedication of a total of 0.28 acres of park area will be dedicated to the city. Dedication of 2.76 acres of Right-of-way within the site to the City. Please see Exhibit D for location of streets to be dedicated.

16. USES

The RPUD development will allow a maximum of 77 single family residential units. No commercial uses allowed within the development.

17. DENSITIES AND INTENSITIES

The intensity and dimensional standards for the project are provided in Exhibit C.

18. DIMENSIONAL STANDARDS

Proposed RPUD Standards:

- A. Streets and entrances will meet the standards as stated in section 8 of this report.
- B. Drainage will meet the standards as stated in section 11C of this report.
- C. Site lighting will be FPL street lights designed to meet City Code requirements.
- D. Standards for building setbacks and allowable uses are shown in Exhibit F.

19. DEVELOPMENT STANDARDS

1. Landscaping standards:

- 2. The landscaping will meet or exceed the City of Pompano Beach Code, Chapter 155, Zoning Code, Article 5 part 2 which pertains to minimum landscaping standards. The developer will provide additional accents at strategic locations within the RPUD to enhance the overall beauty of the entire project. Where possible the shrubs and plantings will be design to drought tolerant Florida native plants and minimize the maintenance requirements for the home owners.
- 3. A perimeter 5' high fence will be installed along the North, East and West boundaries with appropriate landscaping. A 6' high wall will be placed on the South property line to provide additional landscaping to the train tracks.
- 4. Typical and standard required internal landscaping will be provided for individual building structures with street trees being provided as per Chapter 155, Article 5.

5. Traffic Control.

The traffic control within the site will be to Broward County requirements by using signage and striping to control vehicles as well as pedestrian traffic.

20. TYPICAL UNIT ALLOWANCES AND RESTRICTIONS

See Exhibit D for unit allowance and restrictions

See Exhibit E for lot landscape design.

See Exhibit F for typical lot allowance and layout.

21. SUSTAINABILITY ELEMENTS

This project has a unique sustainability attribute because it is a Habitat for Humanity development. Habitat for Humanity works with motivated families that need financial assistance to become home owners. The organization is a non-for-profit group that works with each family to provide the necessary homeownership skills to be financially and mentally responsible to their investment. If the homeowner defaults on the property and cannot live up to their obligations, then Habitat for Humanity will foreclose on the property and sell it to another family that meets the stringent criteria. Habitat for Humanity is committed to Green design initiatives. Their buildings are designed to green standards and the overall site development is designed with green elements to promote the sustainability for the overall community. Habitat for Humanity provides the loans to the homeowners and maintains a vested interest in the community for the life of the loans to insure the community is successful and maintain property values.

22. TREE PRESERVATION

Landscape and tree preservation shall be in accordance with Code Section 155.5203 Landscaping and Code Section 155.5204 Tree Preservation.


23. MODIFICATIONS - PERIMETER FENCE

The Perimeter fence height under Code Section 155.5302 D.2 requires:

- a. No fence or wall within a front yard or a street side yard shall exceed a height of four feet, provided that a fence or wall in a street side yard may be up to six feet in height if set back at least four feet from the street side lot line . Fence posts, including decorative finials, may extend up to six inches above the maximum fence height.
- b. No fence or wall within an interior side yard or a rear yard shall exceed a height of six feet.

This proposed development allows for a five-foot-high decorative fence directly on the perimeter property line abutting NW 6th Avenue and NW 15th Street.

EXHIBIT A
LOCATION MAP



VEGINITY MAP

(N.T.S.)

EXHIBIT "A" - LOCATION MAP

EXHIBIT B

Legal Description

PARCEL "A", **ABYSSINIAN BAPTIST CHURCH OF CHRIST**, ACCORDING TO THE PLAT THEREOF, AS RECORDED IN PLAT BOOK 167, AT PAGE 22 OF THE PUBLIC RECORDS OF BROWARD COUNTY FLORIDA.

TOGETHER WITH;

ALL THAT PART OF THE NW 1/4 OF THE NE 1/4 OF THE NW 1/4 LYING WEST OF AND ADJACENT TO NW 6TH AVENUE, LESS THE F.E.C. RAILROAD RIGHT OF WAY OF THE SOUTH 150 FEET AND NORTH 35 FEET WHICH HAS BEEN DEDICATED FOR ROAD RIGHT-OF-WAY OF NW 15TH STREET, ALL IN SECTION 35, TOWNSHIP 48 SOUTH, RANGE 42 EAST, BROWARD COUNTY, FLORIDA;

AND


THE EAST 100 FEET OF THE E 1/2 OF THE NE 1/4 OF THE NW 1/4 OF THE NW 1/4, EXCEPT THE SOUTH 150 FEET FOR FLORIDA EAST COAST RIGHT-OF-WAY AND EXCEPT THE NORTH 35 FEET THEREOF, DEDICATED FOR STREET RIGHT-OF-WAY, IN SECTION 35, TOWNSHIP 48 SOUTH, RANGE 42 EAST, BROWARD COUNTY, FLORIDA.

SAID LANDS SITUATE IN THE CITY OF POMPANO BEACH, BROWARD COUNTY, FLORIDA, AND CONTAIN 9.035 ACRES, MORE OR LESS.

Folio # 484235750010 & 4842 35 75 0010 & 4842 35 00 0280

EXHIBIT B
SURVEY

EXHIBIT B



SCALE: 1"=60' DATE: 07/01/14					HSQ GROUP, INC. Engineers • Planners • Surveyors 1489 West Palmetto Park Road, Suite 340 Boca Raton, Florida 33486 • (561) 392-0221 CA26258 • LB7924		MAP OF BOUNDARY, TOPOGRAPHIC, AND TREE SURVEY "HABITAT ABYSSINIAN" CITY OF POMPAHO BEACH, BROWARD COUNTY, FLORIDA		PROJECT NUMBER 1406-34	
DRAWN BY: DCL FIELD BOOK: 01384									SHEET NUMBER 1 OF 1	
CHECKED BY: DCW SURVEY TYPE: BOUNDARY										

EXHIBIT C
INTENSITY AND DIMENSION STANDARDS

EXHIBIT C

INTENSITY AND DIMENSION STANDARDS

INTENSITY AND DIMENSION STANDARDS		RM-12	RPUD	RELIEF AMOUNT	Justification
Lot Area, min. (Square Feet)		7000	2,736	4,264 sf	(1)
Lot Width (Feet)	Lot for Two Story Home	60	36	24	(2)
	Lot for One Story Home		40	20	
Density		12	12	0	
Floor Area per Dwelling, min. (Square Feet)		950	1200	0	
Lot Coverage, max. %		60	60	0	
Individual Lot Pervious Area, min. %		25	25	0	
Overall Pervious Area, min %		25	30	0	
Height, max (feet)		35	35	0	
Front Yard Setback, min (feet)	Lot for One Story Home	25	20	5	(3)
	Lot for two Story Home		25	0	
Street Side Setback, min (feet)		8	10	0	
Interior Yard Setback, min (feet)		8	5	3	(4)
Required Front Yard Pervious Area %		50	40	10	(5)
Rear yard setback, min (Feet)		10	10	0	Allow 10 X 10 uncovered Patio Only-all lots(7)
			5	5	Allow 10'x10' covered patio(6)
			10	0	Allow 10 X 5 Covered Patio (7)

JUSTIFICATION

(1)

The Habitat for Humanity builds single family homes approximately 1200 square feet in size. The units have been designed to fit on a smaller lot to provide more homes for people who need housing.

(2)

Lush landscaping will be provided to enhance the space between homes.

(3)

One story building type units on lots 1-42 have a covered front porch allowing for residents to sit in the front yard and provide neighbor friendly streetscape.
Typical 4', but max 5' porch is within the 25' building setback.

(4)

Lots have minimum 5' side setback allowing for 10' between buildings. Roof overhangs and gutters are within the 5' side setback. No fences or structural equipment allowed on side of building. Various home styles with landscaping will enhance the appearance of the community.

(5)

The 36' wide lot with an 18' wide driveway allows for 50% pervious except for additional sidewalks to the house. The additional walkways are in the front setback and for this reason the 10% reduction is necessary.

(6)

Rear setback to allow 10'x10' covered canopy over patio in rear yard to provide shade for owners while utilizing the backyard for lots 1-28. See Exhibit F for lot allowances in rear setback. All other units meet the 10' rear setback requirement.

(7)


Lots 29 thru 47 have rear yards facing NW 6th Avenue and NW 15th Street.
Front yards faces NW 6th Terrace and NW 14th Court.
Allow homes on NW 15th St. and NW 6th Ave. to be considered rear yards along streets.
Allow 5' high along NW 6th Avenue and NW 15th Street where code requires 4' high fence to provide additional security.

EXHIBIT D
REGULATING PLAN PD

EXHIBIT E
LANDSCAPE PLAN

EXHIBIT "E"

All exterior equipment will be screened on all sides.
Location shown is approximate, equipment may be located in rear or anywhere along side of home.
Hedges used to screen the equipment shall be permitted to grow and be maintained at 6 inches above the equipment to be screened.



See overall landscape plan for street trees locations and species.

SINGLE FAMILY 1 TYPICAL UNIT PLANT LIST

SYMBOL	BOTANICAL NAME	COMMON NAME	CONT.	HEIGHT	SPREAD	SPACING	QUANTITY	NOTES
TREES								
BS	Busera simaruba	Gumbo Limbo	B&B	14'	4'		2	
LI	Lagerstroemia x 'Tuskegee'	Tuskegee Crape Myrtle	B&B	12'	4'		1	Standard
SHRUBS AND GROUND COVER								
CA	Crinum augustum 'Queen Emma'	Queen Emma Lily	15 gallon			as shown	2	
CC	Capparis cynophallophora	Jamaica Caper	3 gallon	24"	24"	24" O.C.	5	
VS	Viburnum odoratissimum	Sweet Viburnum	3 gallon	24"	18"	24" O.C.	7	
CGN	Clusia guttifer 'Nana'	Dwarf Small Leaf Clusia	3 gallon	15"	15"	24" O.C.	19	
SPECIFIED SIZES ARE MINIMUM REQUIREMENTS FOR MATERIAL. CONTAINER SIZE IS FOR REFERENCE ONLY.								
SOD - ST. AUGUSTINE 'FLORATAM' - VERIFY SQUARE FOOTAGE IN FIELD								

SINGLE FAMILY 1 TYPICAL UNIT PLANTING PLAN
SCALE: 1/16" = 1'-0"



DAVIDSON DESIGN STUDIO, INC.

LANDSCAPE ARCHITECTURE & SITE PLANNING

10610 NW 43rd Street
Coral Springs, Florida 33065
(954) 649-8888
CERTIFICATE # LC26000437

PROJECT:

A RICK CASE HABITAT COMMUNITY

POMPANO BEACH, FLORIDA


HABITAT FOR HUMANITY
3564 NORTH OCEAN BOULEVARD
FT. LAUDERDALE, FLORIDA 33308

DATE:
6/12/2017

SHEET:
PP-1

EXHIBIT "E"

All exterior equipment will be screened on all sides.
Location shown is approximate, equipment may be located in rear or anywhere along side of home.
Hedges used to screen the equipment shall be permitted to grow and be maintained at 6 inches above the equipment to be screened.



SINGLE FAMILY 1 TYPICAL UNIT PLANT LIST

SYMBOL	BOTANICAL NAME	COMMON NAME	CONT.	HEIGHT	SPREAD	SPACING	QUANTITY	NOTES
TREES								
BA	Bulnesia arborea	Verawood	B&B	14'	4'		2	
CO	Cordia sebestena	Orange Geiger	45 gallon	12'	4'		1	Standard
SHRUBS AND GROUND COVER								
CBM	Cordyline fruticosa 'Black Magic'	Black Magic Ti Plant	7 gallon	3'	2'	as shown	2	3 plants/pot
CI	Chrysobalanus icaco 'Red Tip'	Red-Tip Cocoplum	3 gallon	24"	18"	24" O.C.	5	
VS	Viburnum odoratissimum	Sweet Viburnum	3 gallon	24"	18"	24" O.C.	7	
CGN	Clusia guttata 'Nana'	Dwarf Small Leaf Clusia	3 gallon	15"	15"	24" O.C.	19	
SPECIFIED SIZES ARE MINIMUM REQUIREMENTS FOR MATERIAL. CONTAINER SIZE IS FOR REFERENCE ONLY.								
SOD - ST. AUGUSTINE 'FLORATAM' - VERIFY SQUARE FOOTAGE IN FIELD								

SINGLE FAMILY 1 TYPICAL UNIT PLANTING PLAN

SCALE: 1/16" = 1'-0"



Date:

DAVIDSON DESIGN STUDIO, INC.

LANDSCAPE ARCHITECTURE & SITE PLANNING

10610 NW 43rd Street
Coral Springs, Florida 33065
(954) 649-8888
CERTIFICATE # LC26000437

PROJECT:

A RICK CASE HABITAT COMMUNITY

POMPANO BEACH, FLORIDA


HABITAT FOR HUMANITY
3564 NORTH OCEAN BOULEVARD
FT. LAUDERDALE, FLORIDA 33308

DATE:
6/12/2017

SHEET:
PP-1A

EXHIBIT "E"

All exterior equipment will be screened on all sides.
Location shown is approximate, equipment may be located in rear or anywhere along side of home.
Hedges used to screen the equipment shall be permitted to grow and be maintained at 6 inches above the equipment to be screened.



See overall landscape plan for street trees locations and species.

SINGLE FAMILY 1 CORNER LOT PLANT LIST

SYMBOL	BOTANICAL NAME	COMMON NAME	CONT.	HEIGHT	SPREAD	SPACING	QUANTITY	NOTES
TREES								
BA	Bulnesia arborea	Verawood	B&B	14'	4'		1	
QV	Quercus virginiana	Live Oak		14'	4'		3	Containergrown
LI	Lagerstroemia x 'Tuskegee'	Tuskegee Cape Myrtle	B&B	12'	4'		1	Standard
CB	Cordia alliodora	White Geiger Tree	B&B	10'	3'		1	Standard
SHRUBS AND GROUND COVER								
CQ	Clerodendron quadriloculare	Starburst Clerodendron	7 gallon	3'	3'	as shown	2	
CC	Capparis cynophallophora	Jamaica Caper	3 gallon	24"	24"	24" O.C.	20	
VS	Viburnum odoratissimum	Sweet Viburnum	3 gallon	24"	18"	24" O.C.	7	
CGN	Clusia guttifera 'Nana'	Dwarf Small Leaf Clusia	3 gallon	15"	15"	24" O.C.	19	

SPECIFIED SIZES ARE MINIMUM REQUIREMENTS FOR MATERIAL. CONTAINER SIZE IS FOR REFERENCE ONLY.
SOD - ST. AUGUSTINE 'FLORATAM' - VERIFY SQUARE FOOTAGE IN FIELD

SINGLE FAMILY 1 TYPICAL UNIT CORNER LOT PLANTING PLAN

SCALE: 1/16" = 1'-0"



Date:

DAVIDSON DESIGN STUDIO, INC.

LANDSCAPE ARCHITECTURE & SITE PLANNING

10610 NW 43rd Street
Coral Springs, Florida 33065
(954) 649-6888
CERTIFICATE # LC26000437

PROJECT:

A RICK CASE HABITAT COMMUNITY

POMPANO BEACH, FLORIDA

HABITAT FOR HUMANITY


3564 NORTH OCEAN BOULEVARD
FT. LAUDERDALE, FLORIDA 33308

DATE:
6/12/2017

SHEET:
PP-2

EXHIBIT "E"

All exterior equipment will be screened on all sides.
Location shown is approximate, equipment may be located in rear or anywhere along side of home.
Hedges used to screen the equipment shall be permitted to grow and be maintained at 6 inches above the equipment to be screened.



See overall landscape plan for street trees locations and species.

SINGLE FAMILY 1 CORNER LOT PLANT LIST

SYMBOL	BOTANICAL NAME	COMMON NAME	CONT.	HEIGHT	SPREAD	SPACING	QUANTITY	NOTES
TREES								
BA	Bulnesia arborea	Verawood	B&B	14'	4'		1	
QV	Quercus virginiana	Live Oak		14'	4'		2	Container grown
SS	Senna surrantensis	Glaucous Cassia	B&B	10'	3'		1	Standard
SHRUBS AND GROUND COVER								
CBM	Cordyline fruticosa 'Black Magic'	Black Magic Ti Plant	7 gallon	3'	3'	as shown	1	3 plants/pot
CI	Chrysobalanus icaco 'Red Tip'	Red-Tip Cocoplum	3 gallon	24"	18"	24" O.C.	20	
VS	Viburnum odoratissimum	Sweet Viburnum	3 gallon	24"	18"	24" O.C.	7	
CGN	Clusia guttifera 'Nana'	Dwarf Small Leaf Clusia	3 gallon	15"	15"	24" O.C.	19	
PS	Philodendron selloum	Split Leaf Philodendron	7 gallon	30"	30"	as shown	1	

SPECIFIED SIZES ARE MINIMUM REQUIREMENTS FOR MATERIAL. CONTAINER SIZE IS FOR REFERENCE ONLY.
SOD - ST. AUGUSTINE 'FLORATAM' - VERIFY SQUARE FOOTAGE IN FIELD

SINGLE FAMILY 1 TYPICAL UNIT CORNER LOT PLANTING PLAN
SCALE: 1/16" = 1'-0"



DAVIDSON DESIGN STUDIO, INC.

LANDSCAPE ARCHITECTURE & SITE PLANNING

10610 NW 43rd Street
Coral Springs, Florida 33065
(954) 649-6888
CERTIFICATE # LC26000437

PROJECT:

A RICK CASE HABITAT COMMUNITY


POMPANO BEACH, FLORIDA

HABITAT FOR HUMANITY
3564 NORTH OCEAN BOULEVARD
FT. LAUDERDALE, FLORIDA 33308

DATE:
6/12/2017

SHEET:
PP-2A

EXHIBIT "E"



See overall landscape plan for street tree locations and species.

All exterior equipment will be screened on all sides. Location shown is approximate, equipment may be located in rear or anywhere along side of home. Hedges used to screen the equipment shall be permitted to grow and be maintained at 6 inches above the equipment to be screened.

SINGLE FAMILY 2 TYPICAL UNIT PLANT LIST

SYMBOL	BOTANICAL NAME	COMMON NAME	CONT.	HEIGHT	SPREAD	SPACING	QUANTITY	NOTES
TREES								
BS	Bursaria sinensis	Gumbo Limbo	B&B	14'	4'		1	Standard
IA	Ilex attenuata 'East Palatka'	East Palatka Holly	B&B	14'	4'		1	Standard
LI	Lagerstroemia x 'Tuskegee'	Tuskegee Crape Myrtle	B&B	12'	4'		1	Standard
SHRUBS AND GROUND COVER								
CA	Crinum augustum 'Queen Emma'	Queen Emma Lily	15 gallon				2	
CI	Chrysobalanus icaco 'Red Tip'	Red-Tip Cocoplum	3 gallon	24"	18"	24" O.C.	7	
FGI	Ficus microcarpa 'Green Island'	Green Island Ficus	3 gallon	12"	12"	18" O.C.	9	
SAT	Schefflera arboricola 'Trinette'	Trinette	3 gallon	24"	18"	24" O.C.	5	

SPECIFIED SIZES ARE MINIMUM REQUIREMENTS FOR MATERIAL. CONTAINER SIZE IS FOR REFERENCE ONLY.
SOD - ST. AUGUSTINE 'FLORATAM' - VERIFY SQUARE FOOTAGE IN FIELD

SINGLE FAMILY 2 TYPICAL UNIT PLANTING PLAN

SCALE: 1/16" = 1'-0"



DAVIDSON DESIGN STUDIO, INC.

LANDSCAPE ARCHITECTURE & SITE PLANNING

10610 NW 43rd Street
Coral Springs, Florida 33065
(954) 649-6888
CERTIFICATE # LC26000437

PROJECT:

A RICK CASE HABITAT COMMUNITY

POMPANO BEACH, FLORIDA


HABITAT FOR HUMANITY

3564 NORTH OCEAN BOULEVARD
FT. LAUDERDALE, FLORIDA 33308

DATE:
6/12/2017

SHEET:
PP-3

EXHIBIT "E"



All exterior equipment will be screened on all sides. Location shown is approximate, equipment may be located in rear or anywhere along side of home. Hedges used to screen the equipment shall be permitted to grow and be maintained at 6 inches above the equipment to be screened.

SINGLE FAMILY 2 TYPICAL UNIT PLANT LIST

SYMBOL	BOTANICAL NAME	COMMON NAME	CONT.	HEIGHT	SPREAD	SPACING	QUANTITY	NOTES
TREES								
SM	Swietenia mahagoni	Mahogany	B&B	14'	4'		1	
SS	Senna surattensis	Glaucous Cassia	B&B	14'	4'		1	Standard
TH	Tabebuia heterophylla	Pink Trumpet Tree	B&B	12'	4'		1	Standard
SHRUBS AND GROUND COVER								
CF	Cordyline fruticosa	Ti Plant	7 gallon	3'	2'	as shown	2	3 plants/pot
CI	Chrysobalanus icaco 'Red Tip'	Red-Tip Cocoplum	3 gallon	24"	18"	24" O.C.	7	
FGI	Ficus microcarpa 'Green Island'	Green Island Ficus	3 gallon	12"	12"	18" O.C.	9	
SAT	Schefflera arboricola 'Trinette'	Trinette	3 gallon	24"	18"	24" O.C.	5	

SPECIFIED SIZES ARE MINIMUM REQUIREMENTS FOR MATERIAL. CONTAINER SIZE IS FOR REFERENCE ONLY.
SOD - ST. AUGUSTINE 'FLORATAM' - VERIFY SQUARE FOOTAGE IN FIELD

SINGLE FAMILY 2 TYPICAL UNIT PLANTING PLAN

SCALE: 1/16" = 1'-0"



DAVIDSON DESIGN STUDIO, INC.

LANDSCAPE ARCHITECTURE & SITE PLANNING

10610 NW 43rd Street
Coral Springs, Florida 33065
(954) 649-6888
CERTIFICATE # LC26000437

PROJECT:

A RICK CASE HABITAT COMMUNITY

POMPANO BEACH, FLORIDA


HABITAT FOR HUMANITY
3564 NORTH OCEAN BOULEVARD
FT. LAUDERDALE, FLORIDA 33308

DATE:
6/12/2017

SHEET:
PP-3A

All exterior equipment will be screened on all sides.
Location shown is approximate, equipment may be located in rear or anywhere along side of home.
Hedges used to screen the equipment shall be permitted to grow and be maintained at 6 inches above the equipment to be screened.

EXHIBIT "E"



See overall landscape plan for street tree locations and species.

SINGLE FAMILY 2 CORNER LOT PLANT LIST

SYMBOL	BOTANICAL NAME	COMMON NAME	CONT.	HEIGHT	SPREAD	SPACING	QUANTITY	NOTES
TREES								
BA	Bulnesia arborea	Verawood	B&B	14'	4'		1	Container Grow
QV	Quercus virginiana	Live Oak	B&B	14'	4'		2	Container Grow
LI	Lagerstroemia x 'Tuskegee'	Tuskegee Crape Myrtle	B&B	12'	4'		1	Standard
CB	Cordia alliodora	White Gelger Tree	B&B	10'	3'		1	
SHRUBS AND GROUND COVER								
PM	Podocarpus macrophyllus	Maki	7 gallon	4'	24"	as shown	2	column, full
CI	Chrysobalanus icaco 'Red Tip'	Red-Tip Cocoplum	3 gallon	24"	18"	24" O.C.	23	
FGI	Ficus microcarpa 'Green Island'	Green Island Ficus	3 gallon	12"	12"	18" O.C.	9	
VS	Viburnum odoratissimum	Sweet Viburnum	3 gallon	24"	18"	24" O.C.	7	

SPECIFIED SIZES ARE MINIMUM REQUIREMENTS FOR MATERIAL. CONTAINER SIZE IS FOR REFERENCE ONLY.
SOD - ST. AUGUSTINE 'FLORATAM' - VERIFY SQUARE FOOTAGE IN FIELD

SINGLE FAMILY 2 TYPICAL UNIT CORNER LOT PLANTING PLAN
SCALE: 1/16" = 1'-0"



DAVIDSON DESIGN STUDIO, INC.

LANDSCAPE ARCHITECTURE & SITE PLANNING

10610 NW 43rd Street
Coral Springs, Florida 33065
(954) 649-6888
CERTIFICATE # LC26000437

PROJECT:

A RICK CASE HABITAT COMMUNITY

POMPANO BEACH, FLORIDA

HABITAT FOR HUMANITY


3564 NORTH OCEAN BOULEVARD
FT. LAUDERDALE, FLORIDA 33308

DATE:
6/12/2017

SHEET:
PP-4

All exterior equipment will be screened on all sides.
Location shown is approximate, equipment may be located in rear or anywhere along side of home.
Hedges used to screen the equipment shall be permitted to grow and be maintained at 6 inches above the equipment to be screened.

EXHIBIT "E"



See overall landscape plan for street tree locations and species.

SINGLE FAMILY 2 CORNER LOT PLANT LIST

SYMBOL	BOTANICAL NAME	COMMON NAME	CONT.	HEIGHT	SPREAD	SPACING	QUANTITY	NOTES
TREES								
BA	Bulnesia arborea	Verawood	B&B	14'	4'		2	Container Grow
IA	Ilex attenuata 'East Palatka'	East Palatka Holly	B&B	14'	4'		1	Container Grow
CO	Cordia sebestena	Orange Geiger Tree	B&B	12'	4'		1	Standard
CB	Cordia bolssleri	White Geiger Tree	B&B	10'	3'		1	
SHRUBS AND GROUND COVER								
PM	Podocarpus macrophyllus	Maki	7 gallon	4'	24"	as shown	2	column, full
CC	Capparis cynophallophora	Jamaica Caper	3 gallon	24"	24"	24" O.C.	23	
CV	Codiaeum variegatum 'Mammy'	Mammy Croton	3 gallon	18"	12"	24" O.C.	9	
VS	Viburnum odoratissimum	Sweet Viburnum	3 gallon	24"	18"	24" O.C.	7	

SPECIFIED SIZES ARE MINIMUM REQUIREMENTS FOR MATERIAL. CONTAINER SIZE IS FOR REFERENCE ONLY.
SOD - ST. AUGUSTINE 'FLORATAM' - VERIFY SQUARE FOOTAGE IN FIELD

SINGLE FAMILY 2 TYPICAL UNIT CORNER LOT PLANTING PLAN
SCALE: 1/16" = 1'-0"



DAVIDSON DESIGN STUDIO, INC.

LANDSCAPE ARCHITECTURE & SITE PLANNING

10610 NW 43rd Street
Coral Springs, Florida 33065
(954) 649-8888
CERTIFICATE # LC26000437

PROJECT:

A RICK CASE HABITAT COMMUNITY

POMPANO BEACH, FLORIDA


HABITAT FOR HUMANITY

3564 NORTH OCEAN BOULEVARD
FT. LAUDERDALE, FLORIDA 33308

DATE:
6/12/2017


SHEET:
PP-4A

EXHIBIT F
TYPICAL RESIDENTIAL PLAN




WINDOWS ARE ALLOWED ON ALL SIDES OF BUILDING

EXHIBIT F-1 TYPICAL RESIDENTIAL PLAN TYPE A (LOTS 1 - 18)




WINDOWS ARE ALLOWED ON ALL SIDES OF BUILDING

EXHIBIT F-3 TYPICAL RESIDENTIAL PLAN TYPE C (LOT 28)




**EXHIBIT F-4 TYPICAL RESIDENTIAL PLAN
TYPE D (LOTS 29 - 42)**



WINDOWS ARE ALLOWED ON
ALL SIDES OF BUILDING

**EXHIBIT F-5 TYPICAL RESIDENTIAL PLAN
TYPE E (LOTS 44-46, 49-51, 54-56,
59-61, 64-66, 69-71, 74-76)**





WINDOWS ARE ALLOWED ON
ALL SIDES OF BUILDING

**EXHIBIT F-6 TYPICAL RESIDENTIAL PLAN
TYPE F (LOT 43)**

EXHIBIT G
PEDESTRIAN CIRCULATION AND
RECREATIONAL OPEN SPACE

EXHIBIT G



VEICINITY MAP
(N.T.S.)

LEGEND



PROPOSED PEDESTRIAN CIRCULATION

- SIDEWALKS
- WALKWAYS
- FITNESS TRAIL



PROPOSED RECREATION/OPEN SPACE

- OPEN SPACE
- PLAYGROUND

NO.	DATE	BY	REVISION

Designed by: _____ Date: _____
 Drawn by: _____ Date: _____
 Checked by: _____ Date: _____

Approved by: _____
 Registered Engineer Number _____
 State of Florida




HSQ GROUP, INC.
 Engineers - Planners - Surveyors
 1400 West Palm Beach Road, Suite 340
 Boca Raton, Florida 33486 - 561.362.0221
 C00009 - L07104

A RICK CASE HABITAT COMMUNITY
 CONCEPTUAL MASTER PLAN
 PEDESTRIAN CIRCULATION, RECREATION, OPEN SPACE

PROJECT NUMBER
 14068-34
 SHEET NUMBER
 EXHIBIT G

EXHIBIT H
BUILDING USE PLAN

EXHIBIT H



VEGINITY MAP
(N.T.S.)

LEGEND

-  LANDSCAPE BUFFER
LANDSCAPE AREA
-  ROAD NETWORK
-  ONE AND TWO STORY UNITS
-  TRANSITION AREA (LANDSCAPE,
SIDEWALK, DRIVE)
-  PEDESTRIAN ACCESS

F.E.C. RAILROAD RIGHT-OF-WAY



HSQ GROUP, INC.
Engineers • Planners • Surveyors
1499 West Palm Beach Park Road, Suite 340
Boca Raton, Florida 33486 • 561.392.0021
C28289 - LB7924

A RICK CASE HABITAT COMMUNITY
BUILDING USE PLAN



PROJECT NUMBER
14068-34
SHEET NUMBER
EXHIBIT H

Designed by: _____ Date: _____
Drawn by: _____ Date: _____
Checked by: _____ Date: _____

Reviewed by: _____ Date: _____
Professional Engineer/Planner/Architect
State of Florida

EXHIBIT I
SCHMATIC UTILITIES LAYOUT

EXHIBIT I



VEICINITY MAP
(N.T.S.)

LEGEND

- PROPOSED STORM DRAINAGE
- PROPOSED WATER MAIN
- PROPOSED SANITARY SEWER
- PROPOSED RECLAIMED WATER

NO.	DATE	BY	REVISION

Designed by:	Date:	Approved by:
Drawn by:	Date:	
Checked by:	Date:	Registered Engineer Number
		State of Florida





HSQ GROUP, INC.
Engineers · Planners · Surveyors
1488 West Palmato Park Road, Suite 340
Boca Raton, Florida 33438 · 561.362.6221
C00000000 · L017504

A RICK CASE HABITAT COMMUNITY
CONCEPTUAL MASTER PLAN
SCHEMATIC UTILITIES LAYOUT

PROJECT NUMBER
14088-34
SHEET NUMBER
EXHIBIT I

EXHIBIT J
UTILITIES PLAN

EXHIBIT J



VEGINITY MAP
(N.T.S.)

NOTE: WATER AND SEWER LINES
WILL NOT BE LOCATED WITHIN
LANDSCAPE AREAS

NO.	DATE	BY	REVISION

Designed by: _____ Date: _____
 Drawn by: _____ Date: _____
 Checked by: _____ Date: _____
 Registered Engineer Number: _____
 State of Florida: _____



HSQ GROUP, INC.
 Engineers · Planners · Surveyors
 1400 West Palmetto Park Road, Suite 300
 Boca Raton, Florida 33486 · 561.362.0221
 C06009 · LSP1604

A RICK CASE HABITAT COMMUNITY
 UTILITIES PLAN CONNECTIONS

PROJECT NUMBER
14069-34
 SHEET NUMBER
EXHIBIT J

**EXHIBIT K
PHASING PLAN**




EXHIBIT "K"

NO.	DATE	BY	REVISIONS	NO.	DATE	BY	REVISIONS

Designed by:	JH	Date:	01/15
Drawn by:	JLS	Date:	01/15
Checked by:	JH	Date:	01/15



HSQ GROUP, INC.
Engineers - Planners - Surveyors
1489 West Palmetto Park Road, Suite 340
Boca Raton, Florida 33486 - 961.392.0221
C28058 - L87924

A RICK CASE HABITAT COMMUNITY
PHASING PLAN



SCALE:	1" = 40'
PROJECT NUMBER:	1406-34
SHEET NUMBER:	PH1A-1
DATE:	01/15
APPROVED BY:	JAY HUBBARD, P.E.
REGISTERED ENGINEER NO.:	14611
STATE OF FLORIDA:	

PHASE I

- PERIMETER LANDSCAPING
- PERIMETER WALL
- PERIMETER FENCE
- INFRASTRUCTURE
- 1st. LIFT OF ASPHALT

PHASE II (A)

- 7 (1 STORY)
- 5 (2 STORY)

PHASE II (B)

- PARK

PHASE III

- 7 (1 STORY)
- 5 (2 STORY)

PHASE IV

- 7 (1 STORY)
- 10 (2 STORY)

PHASE IV (A)

- VERTICAL COMPONENT OF PARK REQUIRED PRIOR TO 70% BUILDOUT.

PHASE V

- 8 (1 STORY)
- 10 (2 STORY)

PHASE VI

- 13 (1 STORY)
- 5 (2 STORY)