

Project:2400 E Atlantic

Flood Routing Description:Pre-Development Calculations

Client :Portman Holdings

Design Engineer :Bryan Baldwin

Project Address / Location :2400 East Atlantic Blvd

Section/Township/Range:Section 05, Township 48S, Range 43E

Surfacewater License:

FEMA FIRM Information:12011X0376J

Project Description:A mixed-use building with ground floor commercial, approximately 350 units, and structured parking,

Date: 05/13/2025

Job Number: 14267.00

City: Pompano Beach

County: Broward

State: Florida

DRC

PZ25-12000001

08/06/2025

Total Drainage Basin:0.238 Acres

Hydrogeologic Information :

Table 1.	1 Day Storm Event			3 Day Storm Event		
RAINFALL DATA	Rainfall Inches	Runoff Inches	Runoff Ac-Ft	Rainfall Inches	Runoff Inches	Runoff Ac-Ft
100 Year Return Period						
25 Year Return Period						
10 Year Return Period	9.5	0.13	0.002			
5 Year Return Period	7.8	5.42	0.107	10.6	8.07	0.160
3 Year Return Period						
5 Yr Return Period - 1 Hr	3.2	1.40	0.028			

Runoff estimation - USDA SCS formula

$$\text{Runoff (in)} Q=\frac{(P-0.2S)^2}{P+0.8S}$$

Where: P = accumulated rainfall (in.)
S = Soil Storage Value

Table 2. SUMMARY OF FLOOD ROUTING	Agency maps	SBUH Calculated with Q-1 Day Storm		SBUH Calculated with Q-3 Day Storm		SBUH Calculated *Zero Q-3 Day Storm		Calc. 5Yr 1 hour Peak Stage (ft)
		Peak Stage(ft)	Peak Q (CFS)	Peak Stage(ft)	Peak Q (CFS)	Peak Stage(ft)	Peak Q (CFS)	
100 Year Return Period								Zero Q (Water Budget)
25 Year Return Period								
10 Year Return Period		5.19	0.00					
5 Year Return Period		5.05	0.00	5.27	0.00	5.27	0.00	4.57
3 Year Return Period								

For 5 yr - 1 hr rainfall, Calculate 5 yr Vol by subtracting Exfil vol in inches from 5 yr 1 h rainfall, then calc Runoff using SCS formula. From stage storage table find Zero Discharge Stage. Uses Max. Elev of Lookup Stage or highest top of EXFIL trench. If exfil vol exceeds 5 year 1 hour vol. Uses Max. Elev of highest top of EXFIL trench.

* Zero Q indicates there is no offsite discharge included in the calculations (only Exfil Trench and Wells). Hypothetical stage calc. for PRE-POST Analysis.

Table 3. WATER QUALITY STORAGE REQUIREMENTS:

Based on Total Drainage Basin Acreage	Ac-Ft
1" x Basin Area	0.020
2.5" x WQPI x (Basin Area 1.41 Inches	0.028
Required Wet Detention (Total basin incl Offsite)	
0.5" Pretreatment-Com. Prjs,x(Basin Area - water area)	0.010
Credit for Inlets in Grass Areas, GAC=0.2" x (TDA	0.004
	N

Table 4. WATER QUALITY STORAGE SOURCE	Basin Storage Elev. (Ac-Ft)	WQ Eq WDV (Ac-Ft)	WQ Eq WDV Inches
Retention (RV) @			
Dry Det. (DDV) @			
Wet Det. (WDV) @			
Equiv WDV=WDV+RV/.5+DDV/.75)		0.000	
Exfil Trench Storage	0.000	0.000	
Total WQ EQ WDV - Provided		0.000	
Total WQ EQ WDV - Required		0.028	1.41

Exfil Vol. in Stage Storage =

(Ac-FT)	(Inches)
0.000	0.00

Project: 2400 E Atlantic
Flood Routing Description: Pre-Development Calculations

Date: 05/13/2025

DRC

Client : Portman Holdings Job Number: 14267.00

PZ25-12000001

08/06/2025

Routing Results from Analysis WITHOUT Offsite Discharge

Table 9. STAGE - DISCHARGE INFORMATION 5 - YEAR STORM - Zero Offsite Discharge

TIME STEP (HOUR)	Rain Fall RATIO	Rain C*P (IN)	Q Scs (IN)	Inst Q In (CFS)	Sbuh Q (CFS)	Tot Q In (AC-FT)	Sumq Out (AC-FT)	Stored Vol (AC-FT)	Stage Lk-Up (FEET)	Inst Q Lkup (CFS)	Avg. Q Out (CFS)	Step Qout (AC-FT)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	1.50	0.00	0.00	0.00
4.00	0.02	0.19	0.00	0.00	0.00	0.00	0.00	0.00	1.50	0.00	0.00	0.00
8.00	0.05	0.38	0.00	0.00	0.00	0.00	0.00	0.00	1.50	0.00	0.00	0.00
12.00	0.07	0.57	0.00	0.00	0.00	0.00	0.00	0.00	4.00	0.00	0.00	0.00
16.00	0.10	0.75	0.02	0.00	0.00	0.00	0.00	0.00	4.01	0.00	0.00	0.00
20.00	0.12	0.95	0.07	0.00	0.00	0.00	0.00	0.00	4.03	0.00	0.00	0.00
24.00	0.15	1.14	0.13	0.01	0.00	0.00	0.00	0.00	4.06	0.00	0.00	0.00
28.00	0.18	1.42	0.25	0.01	0.01	0.00	0.00	0.00	4.12	0.00	0.00	0.00
32.00	0.22	1.69	0.38	0.01	0.01	0.01	0.00	0.01	4.20	0.00	0.00	0.00
36.00	0.25	1.96	0.54	0.01	0.01	0.01	0.00	0.01	4.29	0.00	0.00	0.00
40.00	0.29	2.24	0.71	0.01	0.01	0.01	0.00	0.01	4.39	0.00	0.00	0.00
44.00	0.32	2.52	0.90	0.02	0.01	0.02	0.00	0.02	4.50	0.00	0.00	0.00
48.00	0.36	2.79	1.10	0.01	0.01	0.02	0.00	0.02	4.52	0.00	0.00	0.00
52.00	0.40	3.14	1.36	0.02	0.02	0.03	0.00	0.03	4.56	0.00	0.00	0.00
56.00	0.50	3.86	1.93	0.05	0.04	0.03	0.00	0.03	4.62	0.00	0.00	0.00
58.00	0.57	4.45	2.42	0.07	0.06	0.04	0.00	0.04	4.67	0.00	0.00	0.00
59.00	0.63	4.89	2.79	0.10	0.08	0.05	0.00	0.05	4.71	0.00	0.00	0.00
59.50	0.68	5.27	3.13	0.16	0.11	0.05	0.00	0.05	4.73	0.00	0.00	0.00
59.75	0.85	6.59	4.32	1.14	0.23	0.06	0.00	0.06	4.76	0.00	0.00	0.00
60.00	1.02	7.90	5.53	1.16	0.43	0.07	0.00	0.07	4.82	0.00	0.00	0.00
60.50	1.09	8.46	6.06	0.25	0.44	0.09	0.00	0.09	4.95	0.00	0.00	0.00
61.00	1.13	8.76	6.34	0.13	0.33	0.10	0.00	0.10	5.03	0.00	0.00	0.00
62.00	1.18	9.16	6.72	0.08	0.18	0.12	0.00	0.12	5.11	0.00	0.00	0.00
64.00	1.24	9.64	7.18	0.05	0.07	0.14	0.00	0.14	5.18	0.00	0.00	0.00
68.00	1.31	10.20	7.71	0.03	0.03	0.15	0.00	0.15	5.24	0.00	0.00	0.00
72.00	1.36	10.57	8.07	0.02	0.02	0.16	0.00	0.16	5.27	0.00	0.00	0.00
Peak stage						5.27	At hour	72.00				
Peak discharge						0.00	At hour	72.00				

Project: 2400 E Atlantic
Pre-Development Calculations
Flood Routing Description:
Client : Portman Holdings

Date: 05/13/2025

DRC

Job Number: 14267.00

PZ25-12000001

Total Drainage Basin: 0.238 Acres
Water Table Elevation = 1.50 Feet
Time of Conc. (hr.) = 1.00
Calculated weighted soil (s) 2.50 Soil Storage Value (S) = Storage under pervious area / Total Area
Calculated CN value 80.0 Soil Storage under pavement and buildings is not considered in computations

Y	Y/N -Do you want to limit the Exfiltration Trench Vol. to a maximum of 3.28" over the site?
N	Y/N -Deduct EXFIL Vol. from Rainfall amount rather than include Vol. in Stage Storage table
Y	Y/N -Use EXFIL Vol. in Stage Storage, up to Water Quality Vol., without safety Factor of 2.

Table 16. STAGE STORAGE TABLE

Stage Elevation (feet)	Storage (Ac-ft)	Storage (CF)
1.50	0.000	0
2.00	0.000	0
2.50	0.000	0
3.00	0.000	0
3.50	0.000	0
4.00	0.000	0
4.50	0.017	733
5.00	0.093	4,058
5.50	0.212	9,242
6.00	0.331	14,425
6.50	0.450	19,609
7.00	0.569	24,793
7.50	0.688	29,976
8.00	0.807	35,160
8.50	0.926	40,344
9.00	1.045	45,527
9.50	1.164	50,711
10.00	1.283	55,895
10.50	1.402	61,078

Compacted Ground storage table					
Depth to water table (Ft)	1.00	2.00	3.00	4.00	
Ground storage(In)	0.45	1.88	4.95	8.18	
Mean depth to ground water table (ft)=		3.25	(Pervious Area)		
Soil Storage Type		Ground Storage Values (In Inches)			
Depth to Ground Water (Ft)		1	2	3	4
* Depressional		0.45	1.58	3.3	5.1
Flatwoods		0.45	1.88	4.05	6.75
Coastal Type		0.45	1.88	4.95	8.18
* (Low Flatwoods & Costal Lowlands)					
Ground Storage Values reflect 25% reduction of Available Storage, to take into account compaction of native soils.					

Project: 2400 E Atlantic
Pre-Development Calculations

Date: 05/13/2025

DRC

Flood Routing Description:

Client : Portman Holdings

Job Number: 14267.00

PZ25-12000001

Table 17. SITE ACREAGE INFORMATION

Input Information								08/06/2025					
LAND USES	Acres	High Elev.	Low Elev.	% Imperv. Paved	% Bldgs.	% Water	Imperv. Paved Acres	Perv. Acres	Bldgs. Acres	Non Bldgs. Acres	Water Lake Acres	Perv. Area Avg. El.	perv. acres * avg el
BASIN TOTALS / AVERAG	0.238	5.00	1.50	56.57	0.00	0.00	0.13	0.10	0.00	0.24	0.00	4.75	
1 Pervious	0.103	5.00	4.50	0	0	0	0.00	0.10	0.00	0.10	0.00	4.75	0.
2 Impervious	0.135	5.00	4.00	100	0	0	0.13	0.00	0.00	0.13	0.00	0.00	0.
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													
14													
15													
16													
17													
18													
19													
20													
21													
22													
23													
24													
25													
26													
27													
28													
29													
30													
31													
32													
33													
34													
35													
36													
37													
38													
39													
BASIN SUBTOTALS / AVG	0.238	5.00	4.00	56.57	0.00	0.00	0.13	0.10	0.00	0.24	0.00	4.75	0.

Table 18. UNDERGROUND STORAGE INFORMATION

Underground Storage	Area (SF)	Top Elev	Bottom Elev	% Voids
1 Underground Storage 1				
2 Underground Storage 2				
3 Underground Storage 3				
4 Underground Storage 4				
5 Underground Storage 5				
BASIN TOTALS / AVERAGE	0.238	5.00	1.50	56.57
Basin % Imper. for Water Quality Purposes =				
Basin % Impervious (incl. Bldg., No lakes)=				

Project: 2400 E Atlantic
Pre-Development Calculations
Flood Routing Description:
Client : Portman Holdings
Detail - Stage - Storage Information

Date: 05/13/2025
Job Number: 14267.00

DRC
PZ25-12000001

Table 19. STAGE - STORAGE INFORMATION		Surface storage (Ac-Ft)										08/06/2025		
LAND USES	Elev.	Elev.	Elev.	Elev.	Elev.	Elev.	Elev.	Elev.	Elev.	Elev.	Elev.	Elev.	Elev.	Elev.
	1.50	2.00	2.50	3.00	3.50	4.00	4.50	5.00	5.50	6.00	6.50	7.00	7.50	
Total Surface Storage	0.000	0.000	0.000	0.000	0.000	0.000	0.017	0.093	0.212	0.331	0.450	0.569	0.688	
Underground Storage	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	
Exfil Trench Storage	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	
TOTAL Storage	0.000	0.000	0.000	0.000	0.000	0.000	0.017	0.093	0.212	0.331	0.450	0.569	0.688	
1 Pervious	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.026	0.078	0.129	0.181	0.233	0.284	
2 Impervious	0.000	0.000	0.000	0.000	0.000	0.000	0.017	0.067	0.135	0.202	0.269	0.337	0.404	
3														
4														
5														
6														
7														
8														
9														
10														
11														
12														
13														
14														
15														
16														
17														
18														
19														
20														
21														
22														
23														
24														
25														
26														
27														
28														
29														
30														
31														
32														
33														
34														
35														
36														
37														
38														
39														
40														
Total Surface Storage	0.00	0.00	0.00	0.00	0.00	0.00	0.02	0.09	0.21	0.33	0.45	0.57	0.69	

Underground Storage

	1.50	2.00	2.50	3.00	3.50	4.00	4.50	5.00	5.50	6.00	6.50	7.00	7.50	
1 Underground Storage 1														
2 Underground Storage 2														
3 Underground Storage 3														
4 Underground Storage 4														
5 Underground Storage 5														
Total Underground Storage	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	
Exfil Trench Storage	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	
TOTAL Storage	0.000	0.000	0.000	0.000	0.000	0.000	0.017	0.093	0.212	0.331	0.450	0.569	0.688	
Stage Elevation	1.50	2.00	2.50	3.00	3.50	4.00	4.50	5.00	5.50	6.00	6.50	7.00	7.50	

Table 20. SOIL - STORAGE INFORMATION
Detail - Soil Storage Information

08/06/2025

	LAND USES	Depth to Water Table	Ground Storage Under Pervious	
			Inches	Ac-Ft
	TOTAL/AVERAGE		5.76	0.05
1	Pervious	3.25	5.76	0.050
2	Impervious	0.00	0.00	0.000
3				
4				
5				
6				
7				
8				
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				
21				
22				
23				
24				
25				
26				
27				
28				
29				
30				
31				
32				
33				
34				
35				
36				
37				
38				
39				
40				
	TOTAL/AVERAGE		5.76	0.050

Soil Storage Value (S) = Storage under pervious area / Total Area
Soil Storage under pavement and buildings is not considered in computations

S=	2.50019918
----	------------