



OCEAN BOULEVARD
STATE ROAD No. A-1-A

50.0' RIGHT OF WAY PER PLAT
40.0' ASPHALT ROAD



FIRE HYDRANT LOCATION EXHIBIT
SCALE = NTS

SECTION A-A
SCALE = NTS

USMAN - 504 S. OCEAN BLVD.
SURFACE WATER MANAGEMENT CALCULATIONS

HORIZONTAL SURFACE LAND USE BREAKDOWN		
LAND USE	AREA	PERCENT
EX BUILDING	0.04	24%
EX PAVEMENT	0.06	38%
EX GREEN	0.06	38%
TOTAL	0.16	100%
AFFECTED AREA		
PROP. BUILDING	0.024	51%
GREEN	0.023	49%
TOTAL	0.047	100%

Water Quality Calculations:

Water Quality Required

A. Compute the first inch of runoff from the entire site.

$$= 1 \text{ inch} \times \text{Total Area} \times (1 \text{ ft} / 12 \text{ in})$$
$$= 0.004 \text{ ac-ft} \quad (\text{CONTROLS})$$

B. Compute 2.5 inches times the percentage of imperviousness.

a. Site Area (SA), for water quality pervious/impervious calculations only

$$SA = \text{Total Area} - (\text{Roof})$$
$$= 0.023 \text{ Acres}$$

b. Impervious Area (IA), for water quality pervious/impervious calculations only

$$IA = \text{Site Area(SA)} - \text{Pervious Area}$$
$$= 0.000 \text{ Acres}$$

c. Percentage of imperviousness for water quality

$$\%imp = (IA / SA) \times 100\%$$
$$= 0.000 \%$$

d. For 2.5 inches times percentage of imperviousness

$$= 2.5 \text{ inches} \times \%imp$$
$$= 0.000 \text{ inches}$$

e. Compute volume required for quality detention

$$= \text{inches to be treated} \times (\text{total site} - \text{lake}) \times (1 \text{ ft} / 12 \text{ in})$$
$$= 0.000 \text{ ac-ft}$$

C. Since the first inch of runoff over the entire site is greater than 2.5 inches times the percentage of impervious, the volume to be treated is:


ac-ft	Cubic feet (C.F.)
0.004	171 (required)

Water Quality Provided

A. Dry retention area storage (Provided)

Area	L (ft)	W (ft)	D (ft)	Volume (c.f.)
15	40	0.75		225

VOLUME PROVIDED = 225 C.F.



Date: September 28, 2021
This item has been digitally signed and sealed by CLIFFORD R. LOUTAN, P.E. on the date adjacent to the seal. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

4577 Nob Hill Road, Suite 102
Sunrise, FL 33351
www.suntecheng.com
Certificate of Auth. #702718-7019
Phone (954) 777-3123
Fax (954) 777-3114

Sun-Tech Engineering, Inc.
Engineers • Planners • Surveyors

STE

REVISIONS BY

PROPERTY OWNER:
ANAM USMAN

PROPERTY ADDRESS:
**504 SOUTH OCEAN BLVD
POMPANO BEACH FL**

TITLE SHEET
ENGINEERING PLAN

ARCHITECT:
LUIS E. URIARTE
Florida Architect License # AR 94107
18100 ATLANTIC BOULEVARD PHONE
786 290 9807 Email: invusa@ive.com

DRAWN BY:
LUIS URIARTE

DATE:
04.06.2021

SCALE:
AS NOTED

PROJECT:

SHEET
001
OF PAGES

AAC
PZ21-12000018
12/07/21