

Multi Service Systems Inc.

General & Mechanical Contractors

3008 SE Darien Road, Port St. Lucie, Florida. 561-213 4133 772-3981047

Quotation For: Miscellaneous Boat Docking Stations. June 23rd, 2017

Attention: Mr. Jeffrey

Dear Jeff,

We hereby propose to supply material, labor and equipment necessary for the construction of (4) docking stations at the locations provided herein for the total sum of \$ 6,437.71

Scope of work:

Location (A) Indian Mound Park- Provide (4) formed and reinforced concrete buttress blocks installed on the intermediate elevation and spaced to incorporate (2) 3" x 10" X 96" CCA treated wood members fastened with stainless hardware to the buttress blocks. Center mount on each wood member (1) 6.0" x 96" horizontal boat fender attached with stainless steel hardware.

Location (B) Officer Scott Park- Provide (2) 3" x 10" X 96" CCA treated wood members fastened with stainless hardware to the 18" Concrete Wall Cap face. Center mount on each wood member (1) 6.0" x 96" horizontal boat fender attached with stainless steel hardware.

Location (C) 16th Street Park- Provide (2) 3" x 10" X 96" CCA treated wood members fastened with stainless hardware to the existing 21" Concrete Wall Cap face. Center mount on each wood member (1) 6.0" x 96" horizontal boat fender attached with stainless steel hardware.

Location (D) Hillsboro Inlet Park- Provide (2) 3" x 10" X 74" CCA treated wood members fastened with stainless hardware to the existing 12" concrete pilings. Center mount on each wood member (1) 6.0" x 74" horizontal boat fender attached with stainless steel hardware.

General Notes;

All hardware shall be Stainless steel and imbedded a minimum of 5 inches.



All top placed wood members to be even with wall cap elevations.

Location (A) to receive 2" x 8" CCA treated planking over the buttress heads to extend existing wall cap elevation.

All work to be done in a trade like manner with a 1 year warrantee on workmanship and product.

Engineering fees if required, Permit fees or hand rails or modifications are not included.

Docking Stations Reference Sketches and locations:



SAME AS ABOVE

Hillsboro Inlet:

