

Permit needed with City of Pompano Beach

Bore:482 ft.  
Footage page 1: 482 ft.

Construction Notes: ( FPL contractor installing conduit)

Loc. 1-7: Install 1 Holophane 144W 4K LED Teardrop with 6' bracket on NEW 37' black octagonal concrete pole.

Loc. 1.5-4.5: Remove existing fixture and bracket on distribution pole.

Loc. A-C, 3.5 & 4.5: Install 2" riser

\*All lights in this page are being fed underground using directional bore and rapid trench.

FPL contractor to install 2" flex pipe and 2" PVC with 24" minimum cover as shown in the drawing using directional bore and rapid trench. Cable to be used is #6 DPX UG. FPL contractor installing hand-holes, pulling cable and doing terminations


Poles on this page to be installed in R/W at around 3ft from EOP.

- Customer responsible for any restoration required. All hand-holes to be 17" unless noted.

Sales Rep: Francisco Arbide

AS-BUILT CREW PRINT				ALL REQUIRED GROUND RODS HAVE BEEN DRIVEN & VERIFIED TO BE WITHIN FPL STANDARDS. VALUES ARE SHOWN AT ALL LOCATIONS.				JOB CERTIFIED COMPLETED AS SHOWN ON THIS AS-BUILT PRINT. MATERIAL CHANGES SHOWN ON RODS				AS-BUILT COPY			
FOREMAN'S SIGNATURE _____ DATE _____				FOREMAN'S SIGNATURE _____ DATE _____				SUPERVISOR'S SIGNATURE _____ DATE _____				INITIALS _____ CERT. DATE _____			
Easement?		Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		Survey/Stake?		Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		Work with SMO?		Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		FPL Pompano Beach Old Pompano. Phase 3 108 New lights & 47 removals 103 NE 8 <sup>th</sup> ST, Pompano Beach 33060			
Tree Work?		Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		Designer/Stake?		Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		CT/Special Mtr?		Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>					
PERMIT REQ'D		City X		County Rd.		County Air		State Road		FAA		Designed by: Thais Garcia Date: 08/13/20 Drawn by: TG Check by: Dwg No. 1 OF 6			
		WMD		RR Xing		DR. Dist.		Transm.							
Requested Tel. Co. Set Poles ?		YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>		Requested Tel. Co. Transfer ?		YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>		Request CAVT Transfer?		YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>		Tele. Attachment Per _____ Telephone Co. Job No. _____			
POLE LINE FEET 0'				DUCT BANK FT. 0'				Rural Location Sec. xx TWP. xx S, RGE. xx E.							
POLE LINE FT. ON TRANSM. POLES 0'				TRENCH FT. 0'				SCALE: N.T.S				St. Lt MAP No. MAP# Pri Map No. xxxxxx			
TLM/LDS MODEL No. -				Map Posting? YES <input checked="" type="checkbox"/> NO <input type="checkbox"/> Posted by:				WR xxxxxx				M/A xx			





Sales Rep: Francisco Arbide

AS-BUILT CREW PRINT				ALL REQUIRED GROUND RODS HAVE BEEN DRIVEN & VERIFIED TO BE WITHIN FPL STANDARDS. VALUES ARE SHOWN AT ALL LOCATIONS.				JOB CERTIFIED COMPLETE AS SHOWN ON THIS AS-BUILT PRINT. MATERIAL CHANGES SHOWN ON ROS				AS-BUILT COPY				
FO REMAN'S SIGNATURE _____ DATE _____				FO REMAN'S SIGNATURE _____ DATE _____				SUPERVISOR'S SIGNATURE _____ DATE _____				INITIALS _____ CERT. DATE _____				
Easement? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		Survey/Stake? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		Work with SMO? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		FPL		Pompano Beach Old Pompano. Phase 3 108 New lights & 47 removals 103 NE 8 <sup>th</sup> ST, Pompano Beach 33060								
Tree Work? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		Designer/Stake? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		CT/Special Mtr? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>												
PERMIT REQ'D	City X WMD	County Rd. RR Xing	County Air DR. Dist.	State Road Transm.	FAA											
Requested Tel. Co. Set Poles ? YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>						Designed by: Thais Garcia Date: 08/13/20										
Requested Tel. Co. Transfer ? YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>						Drawn by: TG Check by: Dwg No. 2 OF 6										
Request CAVT Transfer? YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>						Telephone Co. Job No. _____										
POLE LINE FEET 0'				DUCT BANK FT. 0'				Rural Location Sec. xx TWP. xx S, RGE. xx E.								
POLE LINE FT. ON TRANSM. POLES 0'				TRENCH FT. 0'				SCALE: N.T.S. St. Lt MAP No. MAP# Pri Map No. xxxxxx								
TLM/LDS MODEL No. -		Map Posting? YES <input checked="" type="checkbox"/> NO <input type="checkbox"/> Posted by: _____				WR xxxxxxxx M/A xx										




**DESIGN CRITERIA:**  
MINIMUM ILLUMINATION LEVELS FOR STREETS IS 0.5FC AND THE MAX  
TO MIN RATIO IS LESS THAN 12:1.  
MINIMUM ILLUMINATION LEVELS AT SIDEWALKS IS 0.2FC.

ROADWAY						
SPACING	SYMBOL	MIN/IN/IN	MAX/IN/IN	AVERAGE	MAX/IN/IN	AVG/IN/IN
10'	*	0.5 FC	3.2 FC	1.3 FC	6.40	2.6

SIDEWALK						
SPACING	SYMBOL	MIN/IN/IN	MAX/IN/IN	AVERAGE	MAX/IN/IN	AVG/IN/IN
10'	+	0.2 FC	2.4 FC	0.6 FC	12.0	3.0

Holophane 144W 4K LED Teardrop with 6' bracket  
on NEW 37' black octagonal concrete pole



**Bore: 1,539 ft.**  
**Trench: 293 ft.**  
**Footage page 3: 1,832 ft.**

Sales Rep: Francisco Arbide

<input type="checkbox"/> INACCESSIBLE	<input checked="" type="checkbox"/> 13 kV	<input type="checkbox"/> FUTURE 23 kV	<input type="checkbox"/> 23 kV	<input type="checkbox"/> SALT SPRAY
---------------------------------------	---	---------------------------------------	--------------------------------	-------------------------------------

**Permit needed with City of Pompano Beach**


**Bore: 1,539 ft.  
Trench: 293 ft.  
Footage page 3: 1,832 ft.**

AS-BUILT CREW PRINT 20.5		ALL REQUIRED GROUND RODS HAVE BEEN DRIVEN & VERIFIED TO BE WITHIN PLS STANDARDS. VALUES ARE SHOWN AT ALL LOCATIONS.		JOB CERTIFIED COMPLETED AS SHOWN ON THIS AS-BUILT PRINT. MATERIAL CHANGES SHOWN ON RDS	AS-BUILT COPY		
FOREMAN'S SIGNATURE _____ DATE _____		FOREMAN'S SIGNATURE _____ DATE _____		SUPERVISOR'S SIGNATURE _____ DATE _____	INITIALS _____ CERT. DATE _____		
Easement? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	Survey/Stake? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	Work with SMO? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	FPL	Pompano Beach Old Pompano. Phase 3 108 New lights & 47 removals 103 NE 8 <sup>th</sup> ST, Pompano Beach 33060			
Tree Work? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	Designer/Stake? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	CT/Special Mtr? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>					
CITY X	COUNTY RD.	COUNTY AIR	STATE ROAD				FAA
PERMIT REQ'D WMD	RR XING	DR. DIST.	TRANSM.				
Requested Tel. Co. Set Poles ? YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>		Tele. Attachment Per _____		Designed by: Thais Garcia Date: 08/13/20			
Requested Tel. Co. Transfer ? YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>		Telephone Co. Job No. _____		Drawn by: TG Check by: Dwg No. 3 OF 6			
Request CAVT Transfer? YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>				Rural Location Sec. xx TWP. xx S, RGE. xx E.			
POLE LINE FEET 0'		DUCT BANK FT. 0'		SCALE: N.T.S. St. Lt MAP No. MAP# Pri Map No. xxxxxx			
POLE LINE FT. ON TRANSM. POLES 0'		TRENCH FT. 0'					
TLM/LDS MODEL No. -	Map Posting? YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Posted by:		WR xxxxxxxx M/A xx			









**Construction Notes: ( FPL contractor installing conduit)**

Loc. 65-91: Install 1 Holophane 144W 4K LED Teardrop with 6' bracket on NEW 37' black octagonal concrete pole.

Loc. 27.5-31.5: Remove existing fixture and bracket on distribution pole.

Loc. 32.5-33.5: Remove existing SL pole, fixture and bracket.

Loc. X-B1 & 77: Install 24" hand-hole

Loc. B1-G1, 28.5, 30.5-31.5: Install 2" riser

\*All lights in this page are being fed underground using directional bore and rapid trench.

FPL contractor to install 2" flex pipe and 2" PVC with 24" minimum cover as shown in the drawing using directional bore and rapid trench. Cable to be used is #6 DPX UG. FPL contractor installing hand-holes, pulling cable and doing terminations


Poles on this page to be installed in R/W at around 3ft from EOP.

- Customer responsible for any restoration required. All hand-holes to be 17" unless noted.

Sales Rep: Francisco Arbide

AS-BUILT CREW PRINT		ALL REQUIRED GROUND RODS HAVE BEEN DRIVEN & VERIFIED TO BE WITHIN FPL STANDARDS. VALUES ARE SHOWN AT ALL LOCATIONS.		JOB CERTIFIED COMPLETED AS SHOWN ON THIS AS-BUILT PRINT. MATERIAL CHANGES SHOWN ON RDS.		AS-BUILT COPY	
FOREMAN'S SIGNATURE _____ DATE _____		FOREMAN'S SIGNATURE _____ DATE _____		SUPERVISOR'S SIGNATURE _____ DATE _____		INITIALS _____ CERT. DATE _____	
Easement? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		Survey/Stake? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		Work with SMO? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		<b>FPL</b> Pompano Beach Old Pompano. Phase 3 108 New lights & 47 removals 103 NE 8 <sup>th</sup> ST, Pompano Beach 33060	
Tree Work? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		Designer/Stake? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		CT/Special Mtr? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>			
PERMIT REQ'D	City <input checked="" type="checkbox"/> WMD	County Rd. <input checked="" type="checkbox"/> RR Xing	County Air <input checked="" type="checkbox"/> DR. Dist.	State Road <input checked="" type="checkbox"/> Transm.	FAA <input checked="" type="checkbox"/>		
Requested Tel. Co. Set Poles ? YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>		Requested Tel. Co. Transfer ? YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>		Request CAVT Transfer? YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>		Tele. Attachment Per _____ Telephone Co. Job No. _____	
POLE LINE FEET 0'		DUCT BANK FT. 0'		Designed by: Thais Garcia		Date: 08/13/20	
POLE LINE FT. ON TRANSM. POLES 0'		TRENCH FT. 0'		Drawn by: TG		Check by: _____ Dwg No. 5 OF 6	
TLM/LDS MODEL No. -		Map Posting? YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>		Rural Location Sec. xx TWP. xx S, RGE. xx E.		SCALE: N.T.S. St. Lt MAP No. MAP# Pri Map No. xxxxxx	
		Posted by: _____		WR xxxxxx		M/A xx	





Sales Rep: Francisco Arbide

AS-BUILT CREW PRINT				ALL REQUIREMENTS AND NOTES HAVE BEEN REVIEWED AND VERIFIED TO BE WITHIN FPL STANDARDS, VALUES ARE SHOWN AT ALL LOCATIONS.				JOB CERTIFIED COMPLETE AS SHOWN ON THIS AS-BUILT PRINT. MATERIAL CHANGES SHOWN IN RED.				AS-BUILT COPY																			
FOREMAN'S SIGNATURE _____				DATE _____				FOREMAN'S SIGNATURE _____				DATE _____				SUPERVISOR'S SIGNATURE _____				DATE _____				INITIALS _____				CERT. DATE _____			
Easement? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>				Survey/Stake? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>				Work with SMO? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>				<div style="border: 1px solid black; padding: 5px; display: inline-block;">FPL</div> <div style="margin-left: 20px;"> <p>Pompano Beach Old Pompano. Phase 3</p> <p>108 New lights &amp; 47 removals</p> <p>103 NE 8<sup>th</sup> ST, Pompano Beach 33060</p> </div>																			
Tree Work? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>				Designer/Stake? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>				CT/Special Mtr? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>																							
PERMIT REQ'D		City <input checked="" type="checkbox"/> WMD		County Rd. <input type="checkbox"/> RR Xing		County Air <input type="checkbox"/> DR. Dist.		State Road <input type="checkbox"/> Transm.		FAA <input type="checkbox"/>																					
Requested Tel. Co. Set Poles? YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>								Tele. Attachment Per _____								Designed by: Thais Garcia				Date: 08/13/20											
Requested Tel. Co. Transfer? YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>								Telephone Co. Job No. _____								Drawn by: TG				Check by: _____				Dwg No. 6 OF 6							
Request CAVT Transfer? YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>																Rural Location Sec. xx				TWP. xx				S, RGE. xx				E. xx			
POLE LINE FEET 0'								DUCT BANK FT. 0'								SCALE: N.T.S.				St. Lt MAP No. MAP#				Pri Map No. xxxxxx							
POLE LINE FT. ON TRANSM. POLES 0'								TRENCH FT. 0'								TLM/LDS MODEL No. -				Map Posting? YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>				Posted by: WR xxxxxxxx				M/A xx			